


VOLCANOES AND EARTHQUAKES



Britannica Illustrated Science Library



About the pagination of this eBook

Due to the unique page numbering scheme of this book, the electronic pagination of the eBook does not match the pagination of the printed version. To navigate the text, please use the electronic Table of Contents that appears alongside the eBook or the Search function.

For citation purposes, use the page numbers that appear in the text.

VOLCANOES AND EARTHQUAKES

Britannica Illustrated Science Library

Encyclopædia Britannica, Inc.

Chicago ■ London ■ New Delhi ■ Paris ■ Seoul ■ Sydney ■ Taipei ■ Tokyo

Britannica Illustrated Science Library

© 2008 Editorial Sol 90

All rights reserved.

Idea and Concept of This Work: Editorial Sol 90

Project Management: Fabián Cassan

Photo Credits: Corbis, ESA, Getty Images, Graphic News, NASA, National Geographic, Science Photo Library

Illustrators: Guido Arroyo, Pablo Aschei, Gustavo J. Caironi, Hernán Cañellas, Leonardo César, José Luis Corsetti, Vanina Farías, Joana Garrido, Celina Hilbert, Isidro López, Diego Martín, Jorge Martínez, Marco Menco, Ala de Mosca, Diego Mourellos, Eduardo Pérez, Javier Pérez, Ariel Pirovansky, Ariel Roldán, Marcel Socías, Néstor Taylor, Trebol Animation, Juan Venegas, Coralia Vignau, 3DN, 3DOM studio

Composition and Pre-press Services: Editorial Sol 90

Translation Services and Index: Publication Services, Inc.

Portions © 2008 Encyclopædia Britannica, Inc.

Encyclopædia Britannica, Britannica, and the thistle logo are registered trademarks of Encyclopædia Britannica, Inc.

Britannica Illustrated Science Library Staff

Editorial

Michael Levy, *Executive Editor, Core Editorial*
John Rafferty, *Associate Editor, Earth Sciences*
William L. Hosch, *Associate Editor, Mathematics and Computers*
Kara Rogers, *Associate Editor, Life Sciences*
Rob Curley, *Senior Editor, Science and Technology*
David Hayes, *Special Projects Editor*

Art and Composition

Steven N. Kapusta, *Director*
Carol A. Gaines, *Composition Supervisor*
Christine McCabe, *Senior Illustrator*

Media Acquisition

Kathy Nakamura, *Manager*

Copy Department

Sylvia Wallace, *Director*
Julian Ronning, *Supervisor*

Information Management and Retrieval

Sheila Vasich, *Information Architect*

Production Control

Marilyn L. Barton

Manufacturing

Kim Gerber, *Director*

Encyclopædia Britannica, Inc.

Jacob E. Safra, *Chairman of the Board*

Jorge Aguilar-Cauz, *President*

Michael Ross, *Senior Vice President, Corporate Development*

Dale H. Hoiberg, *Senior Vice President and Editor*

Marsha Mackenzie, *Director of Production*

International Standard Book Number (set):

978-1-59339-797-5

International Standard Book Number (volume):

978-1-59339-800-2

Britannica Illustrated Science Library:


Volcanoes and Earthquakes 2008

Printed in China



www.britannica.com

Volcanoes and Earthquakes



Contents

Continuous Movement

Page 6

Volcanoes

Page 24

Study and Prevention

Page 44

Earthquakes

Page 58

Study and Prevention

Page 74



Kashmir, 2005

Farmer Farid Hussain, 50, grasps the hand of his wife, Akthar Fatma, after the earthquake that rocked the Himalayas on the Indian subcontinent. Eighty thousand people were killed, and thousands of families were left homeless.

The Power of Nature

Some photos speak for themselves. Some gestures communicate more than words ever could, like these clasped hands, which seek comfort in the face of fear of the unknown. The picture was taken Oct. 8, 2005, when aftershocks were still being felt from the strongest earthquake ever to strike Kashmir, in northern India. Those clasped hands symbolize terror and panic; they speak of fragility and

helplessness, of endurance in the face of chaos. Unlike storms and volcanic eruptions, earthquakes are unpredictable, unleashed within seconds, and without warning. They spread destruction and death, forcing millions to flee from their homes. The day after the catastrophe revealed a terrifying scene: debris everywhere, a number of people injured and dead, others wandering desperately, children crying, and over three million survivors seeking help after losing everything. Throughout history Earth has been shaken by earthquakes of greater or lesser violence. These earthquakes have caused great harm. One of the most famous is the earthquake that rocked San Francisco in 1906. Registering 8.3 on the Richter scale, the temblor left nearly three thousand dead and was felt as far away as Oregon to the north, and Los Angeles in southern California.

The purpose of this book is to help you better understand the causes of fractures and the magnitude and violence of the forces deep within the earth. The full-color, illustrated book you hold in your hands contains shocking scenes of cities convulsed by earthquakes and volcanoes, natural phenomena that, in mere seconds, unleash rivers of fire, destroy buildings, highways and bridges, and gas and water lines and leave entire cities without electricity or phone service. If fires cannot be put out quickly, the results are even more devastating. Earthquakes near coastlands can cause tsunamis, waves that spread across the ocean with the speed of an airplane. A tsunami that reaches a coast can

be more destructive than the earthquake itself. On Dec. 26, 2004, the world witnessed one of the most impressive natural disasters ever. An undersea quake with a magnitude of 9 on the Richter scale shook the eastern Indian Ocean, causing tsunamis that reached the coastal areas of eight Asian nations, causing about 230,000 deaths. The earthquake was the fifth strongest since the invention of the seismograph. Satellite images show the region before and after the catastrophe.

Throughout history, nearly all ancient peoples and large societies have thought of volcanoes as dwelling places of gods or other supernatural beings to explain the mountains' fury. Hawaiian mythology, for instance, spoke of Pele, the goddess of volcanoes, who threw out fire to cleanse the earth and fertilize the soil. She was believed to be a creative force. Nowadays, specialists try to find out when a volcano might start to erupt, because within hours after an eruption begins, lava flows can change a lush landscape into a barren wilderness. Not only does hot lava destroy everything in its path, but gas and ash expelled in the explosion also replace oxygen in the air, poisoning people, animals, and plants. Amazingly, life reemerges once again from such scenes of destruction. After a time, lava and ash break down, making the soil unusually fertile. For this reason many farmers and others continue to live near these "smoking mountains," in spite of the latent danger. Perhaps by living so close to the danger zone, they have learned that no one can control the forces of nature, and the only thing left to do is to simply live. ●

Continuous Movement

PAHOEHOE LAVA
A type of Hawaiian lava
that flows down the slopes
of Mt. Kilauea to the sea.

SCORCHING FLOW 8-9

THE LONG HISTORY OF THE EARTH 10-11

STACKED LAYERS 12-13


THE JOURNEY OF THE PLATES 14-15

OCEAN TRENCHES 16-17

WRINKLES IN THE EARTH 18-19

FOLDS 20-21

WHEN FAULTS RESOUND 22-23



In the volatile landscape of Volcano National Park in Hawaii, the beginning and end of life seem to go hand in hand. Outpourings of lava often reach

the sea. When the molten rock enters the water, the lava quickly cools and hardens into rock that becomes part of the coastline. By this process, volcanic islands grow constantly, and

nothing stays the same from one moment to another. One day rivers of lava blaze down the volcano's slopes, and the next day there are new, silver-colored rocks. The ongoing

investigation of lava samples under the microscope helps volcanologists discover the rock's mineral composition and offers clues about how the volcano may behave. ●

Scorching Flow

Most of the Earth's interior is in a liquid and incandescent state at extremely high temperatures. This vast mass of molten rock contains dissolved crystals and water vapor, among other gases, and it is known as magma. When part of the magma rises toward the Earth's surface, mainly through volcanic activity, it is called lava. As soon as it reaches the surface of the Earth or the ocean floor, the lava starts to cool and solidify into different types of rock, according to its original chemical composition. This is the basic process that formed the surface of our planet, and it is the reason the Earth's surface is in constant flux. Scientists study lava to understand our planet better. ●

Streams of Fire


Lava is at the heart of every volcanic eruption. The characteristics of lava vary, depending on the gases it contains and its chemical composition. Lava from an eruption is loaded with water vapor and gases such as carbon dioxide, hydrogen, carbon monoxide, and sulfur dioxide. As these gases are expelled, they burst into the atmosphere, where they create a turbulent cloud that sometimes discharges heavy rains. Fragments of lava expelled and scattered by the volcano are classified as bombs, cinders, and ash. Some large fragments fall back into the crater. The speed at which lava travels depends to a great extent on the steepness of the sides of the volcano. Some lava flows can reach 90 miles (145 km) in length and attain speeds of up to 30 miles per hour (50 km/hr).

INTENSE HEAT

Lava can reach temperatures above 2,200° F (1,200° C). The hotter the lava, the more fluid it is. When lava is released in great quantities, it forms rivers of fire. The lava's advance is slowed down as the lava cools and hardens.

Mineral Composition

Lava contains a high level of silicates, light rocky minerals that make up 95 percent of the Earth's crust. The second most abundant substance in lava is water vapor. Silicates determine lava's viscosity, that is, its capacity to flow. Variations in viscosity have resulted in one of the most commonly used classification systems of lava: basaltic, andesitic, and rhyolitic, in order from least to greatest silicate content. Basaltic lava forms long rivers, such as those that occur in typical Hawaiian volcanic eruptions, whereas rhyolitic lava tends to erupt explosively because of its poor fluidity. Andesitic lava, named after the Andes mountains, where it is commonly found, is an intermediate type of lava of medium viscosity.



Rock Cycle

Once it cools, lava forms igneous rock. This rock, subjected to weathering and natural processes such as metamorphism and sedimentation, will form other types of rocks that, when they sink back into the Earth's interior, again become molten rock. This process takes millions of years and is known as the rock cycle.



SOLID LAVA


Lava solidifies at temperatures below 1,700° F (900° C). The most viscous type of lava forms a rough landscape, littered with sharp rocks; more fluid lava, however, tends to form flatter and smoother rocks.

1,800° F
(1,000° C)

is the average temperature of liquid lava.

TYPES OF LAVA

Basaltic lava is found mainly in islands and in mid-ocean ridges; it is so fluid that it tends to spread as it flows. Andesitic lava forms layers that can be up to 130 feet (40 m) thick and that flow very slowly, whereas rhyolitic lava is so viscous that it forms solid fragments before reaching the surface.



Andesitic Lava

Silicates	63%
Other Content	37%



Rhyolitic Lava

Silicates	68%
Other Content	32%

The Long History of the Earth

The nebular hypothesis developed by astronomers suggests that the Earth was formed in the same way and at the same time as the rest of the planets and the Sun. It all began with an immense cloud of helium and hydrogen and a small portion of heavier materials 4.6 billion years ago. Earth emerged from one of these "small" revolving clouds, where the particles constantly collided with one another, producing very high temperatures. Later, a series of processes took place that gave the planet its present shape. ●

From Chaos to Today's Earth

Earth was formed 4.6 billion years ago. In the beginning it was a body of incandescent rock in the solar system. The first clear signs of life appeared in the oceans 3.6 billion years ago, and since then life has expanded and diversified. The changes have been unceasing, and, according to experts, there will be many more changes in the future.

4.6 BILLION YEARS AGO

FORMATION

The accumulation of matter into solid bodies, a process called accretion, ended, and the Earth stopped increasing in volume.

4.5

BILLION YEARS AGO

COOLING

The first crust formed as it was exposed to space and cooled. Earth's layers became differentiated by their density.

4

BILLION YEARS AGO

METEORITE COLLISION

Meteorite collisions, at a rate 150 times as great as that of today, evaporated the primitive ocean and resulted in the rise of all known forms of life.

3.8

BILLION YEARS AGO
ARCHEAN EON

STABILIZATION

The processes that formed the atmosphere, the oceans, and protolife intensified. At the same time, the crust stabilized, and the first plates of Earth's crust appeared. Because of their weight, they sank into Earth's mantle, making way for new plates, a process that continues today.

THE AGE OF THE SUPER VOLCANOES

Indications of komatite, a type of igneous rock that no longer exists.

60

MILLION YEARS AGO

FOLDING IN THE TERTIARY PERIOD

The folding began that would produce the highest mountains that we now have (the Alps, the Andes, and the Himalayas) and that continues to generate earthquakes even today.

540

MILLION YEARS AGO

PALEOZOIC ERA

FRAGMENTATION

The great landmass formed that would later fragment to provide the origin of the continents we have today. The oceans reached their greatest rate of expansion.

1.0

BILLION YEARS AGO

SUPERCONTINENTS

Rodinia, the first supercontinent, formed, but it completely disappeared about 650 million years ago.

1.8

BILLION YEARS AGO

PROTEROZOIC EON

CONTINENTS

The first continents, made of light rocks, appeared. In Laurentia (now North America) and in the Baltic, there are large rocky areas that date back to that time.

2.2

BILLION YEARS AGO

WARMING

Earth warmed again, and the glaciers retreated, giving way to the oceans, in which new organisms would be born. The ozone layer began to form.

2.3

BILLION YEARS AGO

"SNOWBALL" EARTH

Hypothesis of a first, great glaciation.

Stacked Layers

Every 110 feet (33 m) below the Earth's surface, the temperature increases by 1.8 degrees Fahrenheit (1 degree Celsius). To reach the Earth's center—which, in spite of temperatures above 12,000° F (6,700° C), is assumed to be solid because of the enormous pressure exerted on it—a person would have to burrow through four well-defined layers. The gases that cover the Earth's surface are also divided into layers with different compositions. Forces act on the Earth's crust from above and below to sculpt and permanently alter it. ●

Earth's crust

Earth's crust is its solid outer layer, with a thickness of 3 to 9 miles (4 to 15 km) under the oceans and up to 44 miles (70 km) under mountain ranges. Volcanoes on land and volcanic activity in the mid-ocean ridges generate new rock, which becomes part of the crust. The rocks at the bottom of the crust tend to melt back into the rocky mantle.

THE SOLID EXTERIOR

The crust is made up of igneous, sedimentary, and metamorphic rock, of various typical compositions, according to the terrain.

KEY ● Sedimentary Rock ● Igneous Rock ● Metamorphic Rock

THE CONTINENTAL SHELF
In the area where the oceanic crust comes in contact with a continent, igneous rock is transformed into metamorphic rock by heat and pressure.

THE MID-OCEAN RIDGES
The ocean floor is regenerated with new basaltic rock formed by magma that solidifies in the rifts that run along mid-ocean ridges.

OCEANIC ISLANDS
Some sedimentary rocks are added to the predominantly igneous rock composition.

MOUNTAIN RANGES
Made up of the three types of rock in about equal parts.

CRUST
3-44 miles
(5-70 km)

GRANITIC BATHOLITHS
Plutons can solidify underground as masses of granite.

PLUTONS
Masses of rising magma trapped within the Earth's crust. Their name is derived from Pluto, the Roman god of the underworld.

INTERNAL ROCK
The inside of a mountain range consists of igneous rock (mostly granite) and metamorphic rock.

COASTAL ROCK
Lithified layers of sediments, usually clay and pebbles, that come from the erosion of high mountains.

The Gaseous Envelope

The air and most of the weather events that affect our lives occur only in the lower layer of the Earth's atmosphere. This relatively thin layer, called the troposphere, is up to 10 miles (16 km) thick at the equator but only 4 miles (7 km) thick at the poles. Each layer of the atmosphere has a distinct composition.


Less than 6 miles
(10 km)
TROPOSPHERE
Contains 75 percent of the gas and almost all of the water vapor in the atmosphere.

Less than 31 miles
(50 km)
STRATOSPHERE
Very dry; water vapor freezes and falls out of this layer, which contains the ozone layer.

Less than 62 miles
(100 km)
MESOSPHERE
The temperature is -130° F (-90° C), but it increases gradually above this layer.

Less than 310 miles
(500 km)
THERMOSPHERE
Very low density. Below 155 miles (250 km) it is made up mostly of nitrogen; above that level it is mostly oxygen.

Greater than 310 miles
(500 km)
EXOSPHERE
No fixed outer limit. It contains lighter gases such as hydrogen and helium, mostly ionized.



The Journey of the Plates

When geophysicist Alfred Wegener suggested in 1910 that the continents were moving, the idea seemed fantastic. There was no way to explain the idea. Only a half-century later, plate tectonic theory was able to offer an explanation of the phenomenon. Volcanic activity on the ocean floor, convection currents, and the melting of rock in the mantle power the continental drift that is still molding the planet's surface today. ●

Continental Drift

The first ideas on continental drift proposed that the continents floated on the ocean. That idea proved inaccurate. The seven tectonic plates contain portions of ocean beds and continents. They drift atop the molten mantle like sections of a giant shell. Depending on the direction in which they move, their boundaries can converge (when they tend to come together), diverge (when they tend to separate), or slide horizontally past each other (along a transform fault).

The Hidden Motor

Convection currents of molten rock propel the crust. Rising magma forms new sections of crust at divergent boundaries. At convergent boundaries, the crust melts into the mantle. Thus, the tectonic plates act like a conveyor belt on which the continents travel.

2 inches
(5 cm)

Typical distance the plates travel in a year.

250 MILLION YEARS AGO

The landmass today's continents come from was a single block (Pangea) surrounded by the ocean.



...180 MILLION YEARS AGO

The North American Plate has separated, as has the Antarctic Plate. The supercontinent Gondwana (South America and Africa) has started to divide and form the South Atlantic. India is separating from Africa.



...100 MILLION YEARS AGO

The Atlantic Ocean has formed. India is headed toward Asia, and when the two masses collide, the Himalayas will rise. Australia is separating from Antarctica.




... 60 MILLION YEARS AGO

The continents are near their current location. India is beginning to collide with Asia. The Mediterranean is opening, and the folding is already taking place that will give rise to the highest mountain ranges of today.



250 MILLION YEARS

The number of years it will take for the continents to drift together again.



Cracks in the Ocean Floor

The concept that the ocean floor is spreading was studied for many years: new crust constantly forms at the bottom of the ocean. The ocean floor has deep trenches, plains, and mountain ranges. The mountain ranges are higher than those found on the continents but with different characteristics. The spines of these great mountain ranges,

called mid-ocean ridges, exhibit incredible volcanic activity in rift zones. The rift zones are fissures in relatively narrow regions of the crust, along which the crust splits and spreads. One hundred eighty million years ago, the paleocontinent Gondwana broke apart, forming a rift from which the Atlantic Ocean grew, and is still growing. ●

The Crust Under the Oceans

The constant generation of new ocean crust along rift zones powers a seemingly endless process that generates new lithosphere that is carried from the crest of the ridges, as if on a conveyor belt. Because of this, scientists have calculated that in about 250 million years, the continents will again join and form a new Pangea as they are pushed

by the continually expanding ocean floor. Ocean plates are in contact with land plates at the active boundaries of subduction zones or at passive continental boundaries (continental shelves and slopes). Undersea subduction zones, called ocean trenches, also occur between oceanic plates; these are the deepest places on the planet.

HEIGHTS AND DEPTHS

Deep-ocean basins cover 30 percent of the Earth's surface. The depth of the ocean trenches is greater than the height of the greatest mountain ranges, as shown in the graphic below at left.



29,035 feet (8,850 m)
Highest point
(Mount Everest)



Inside and Outside the Ridge

The abyssal (deep-ocean) plains of the Atlantic are the flattest surfaces on Earth; for thousands of miles, the elevation varies by only about 10 feet (3 m). The plains are made mostly of sediment. Variations in the ocean's depth are mainly the result of volcanic activity, not just within the mid-Atlantic Ridge but elsewhere as well.

1 ATOLLS

Also called coral reefs, atolls are formations of coral deposited around a volcanic cone in warm seas. They form ring-shaped islands.

SOUTH AMERICA

EUROPE

AFRICA

2,900 feet (870 m)
Average land elevation

0 feet (0 m)
Sea level

7,900 feet (2,409 m)
Earth's average elevation

12,102 feet (3,719 m)
Average depth

Magnetic Reversals

The Earth's magnetic field changes direction periodically. The magnetic north pole changes places with the magnetic south pole. Rock that solidified during a period of magnetic polarity reversal was magnetized with a polarity opposite that of newly forming rocks. Rocks whose magnetism corresponds to the present direction of the Earth's magnetic field are said to have normal polarity, whereas those with the opposite magnetic polarity are said to have reversed polarity.

MAGNETISM

Normal magnetism
Reversed magnetism

2 OCEAN MOUNTS

Isolated volcanic cones. Some rise above the ocean's surface to become islands, such as the Azores.

How the Mid-Ocean Ridge Was Formed

A sparry layer of rock several dozen miles wide rises above the rift. As the layer fractures and moves away from the fissure, it solidifies into angled blocks that are parallel to the fissure and separated by dikes. Thus the ocean widens as the ridge spreads. The magma exists in a fluid form 2 miles (3.5 km) below the crest of the ridge.

Asthenosphere

Dikes within host rock

Oceanic lithosphere

Pillow lava

Volcanic smoke

Fumarole

Rising magma

Folding in the Earth's Crust

The movement of tectonic plates causes distortions and breaks in the Earth's crust, especially in convergent plate boundaries. Over millions of years, these distortions produce larger features called folds, which become mountain ranges. Certain characteristic types of terrain give clues about the great folding processes in Earth's geological history. ●


Distortions of the Crust

The crust is composed of layers of solid rock. Tectonic forces, resulting from the differences in speed and direction between plates, make these layers stretch elastically, flow, or break. Mountains are formed in processes requiring millions of years. Then external forces, such as erosion from wind, ice, and water, come into play. If slippage releases rock from the pressure that is deforming it elastically, the rock tends to return to its former state and can cause earthquakes.

1 A portion of the crust subjected to a sustained horizontal tectonic force is met by resistance, and the rock layers become deformed.



2 The outer rock layers, which are often more rigid, fracture and form a fault. If one rock boundary slips underneath another, a thrust fault is formed.



3 The composition of rock layers shows the origin of the folding, despite the effects of erosion.



The Three Greatest Folding Events

The Earth's geological history has included three major mountain-building processes, called "orogenies." The mountains created during the first two orogenies (the Caledonian and the Hercynian) are much lower today because they have undergone millions of years of erosion.




MATERIALS Mudstone, slate, and sandstone, in lithified layers.



Trilobites



MATERIALS Mostly granite, slate, amphibolite, gneiss, quartzite, and schist.



Brachiopods

430 Million Years

CALEDONIAN OROGENY
Formed the Caledonian range. Remnants can be seen in Scotland, the Scandinavian Peninsula, and Canada (which all collided at that time).

300 Million Years

HERCYNIAN OROGENY
Took place between the late Devonian and the early Permian periods. It was more important than the Caledonian Orogeny. It shaped central and western Europe and produced large veins of iron ore and coal. This orogeny gave rise to the Ural Mountains, the Appalachian range in North America, part of the Andes, and Tasmania.

Formation of the Himalayas

The highest mountains on Earth were formed following the collision of India and Eurasia. The Indian Plate is sliding horizontally underneath the Asiatic Plate. A sedimentary block trapped between the plates is cutting the upper part of the Asiatic Plate into segments that are piling on top of each other. This folding process gave rise to the Himalayan range, which includes the highest mountain on the planet, Mount Everest (29,035 feet [8,850 m]). This deeply fractured section of the old plate is called an accretion prism. At that time, the Asian landmass bent, and the plate doubled in thickness, forming the Tibetan plateau.



SOUTHEAST ASIA






Ammonites

60 MILLION YEARS


ALPINE OROGENY
Began in the Cenozoic Era and continues today. This orogeny raised the entire system of mountain ranges that includes the Pyrenees, the Alps, the Caucasus, and even the Himalayas. It also gave the American Rockies and the Andes Mountains their current shape.

MATERIALS
High proportions of sediment in Nepal, batholiths in the Asiatic Plate, and intrusions of new granite: iron, tin, and tungsten.


A COLLISION OF CONTINENTS




60 MILLION YEARS AGO
The Tethys Sea gives way as the plates approach. Layers of sediment begin to rise.



40 MILLION YEARS AGO
As the two plates approach each other, a subduction zone begins to form.



20 MILLION YEARS AGO
The Tibetan plateau is pushed up by pressure from settling layers of sediment.



THE HIMALAYAS TODAY
The movement of the plates continues to fold the crust, and the land of Nepal is slowly disappearing.

Folds

The force that forms the mountains also molds the rocks within them. As the result of millions of years of pressure, the layers of crust fold into strange shapes. The Caledonian Orogeny, which began 450 million years ago, created a long mountain range that joined the Appalachian mountains of the United States to the Scandinavian peninsula. All of northern England was lifted up during this process. The ancient Iapetus Ocean once lay between the colliding continents. Sedimentary rocks from the bed of this ocean were lifted up, and they have kept the same forms they had in the past. ●

Silurian

The name of the geological period in which this folding occurred.

1. **THREE CONTINENTS**
The Caledonian orogeny was formed by the collision of three ancient continents: Laurasia, Gondwana, and Baltica. In between them, the Iapetus Ocean floor contained sediments that now form the bedrock of the coast of Wales.

440
MILLION
YEARS



395
MILLION
YEARS

2. **A MOUNTAIN RANGE**
The long Caledonian range is seen today in the coasts of England, Greenland, and Scandinavia. Since the tectonic movements that created them have ended, they are being worn away and sculpted by constant erosion.

SANDSTONE

LIMESTONE

Composition

Before mountain ranges were lifted up by the collision of ancient continents, constant erosion of the land had deposited large amounts of sediments along their coasts. These sediments later formed the rock that makes up the folding seen here. As that rock's shape clearly shows, tectonic forces compressed the originally horizontal sediments until they became curved. This phenomenon is seen along Cardigan Bay on the ancient coast of Wales.

SANDSTONE

MUDSTONE



WALES, UNITED KINGDOM

Latitude: 51° 30' N
Longitude: 003° 12' W

Place	Cardigan Bay
Length	40 miles (64 km)
Rock	Sedimentary
Fold	Monoclinial

When the Faults Resound

Faults are small breaks that are produced along the Earth's crust. Many, such as the San Andreas fault, which runs through the state of California, can be seen readily. Others, however, are hidden within the crust. When a fault fractures suddenly, an earthquake results. Sometimes fault lines can allow magma from lower layers to break through to the surface at certain points, forming a volcano. ●

Relative Movement Along Fault Lines


Fault borders do not usually form straight lines or right angles; their direction along the surface changes. The angle of vertical inclination is called "dip." The classification of a fault depends on how the fault was formed and on the relative movement of the two plates that

form it. When tectonic forces compress the crust horizontally, a break causes one section of the ground to push above the other. In contrast, when the two sides of the fault are under tension (pulled apart), one side of the fault will slip down the slope formed by the other side of the fault.

1

Normal Fault


This fault is the product of horizontal tension. The movement is mostly vertical, with an overlying block (the hanging wall) moving downward relative to an underlying block (the footwall). The fault plane typically has an angle of 60 degrees from the horizontal.



2

Reverse Fault


This fault is caused by a horizontal force that compresses the ground. A fracture causes one portion of the crust (the hanging wall) to slide over the other (the footwall). Thrust faults (see pages 18-19), are a common form of reverse fault that can extend up to hundreds of miles. However, reverse faults with a dip greater than 45° are usually only a few yards long.



3


Oblique-Slip Fault

This fault has horizontal as well as vertical movements. Thus, the relative displacement between the edges of the fault can be diagonal. In the oldest faults, erosion usually smoothes the differences in the surrounding terrain, but in more recent faults, cliffs are formed. Transform faults that displace mid-ocean ridges are a specific example of oblique-slip faults.



350 miles (566 km)

The distance that the opposite sides of the fault have slipped past each other, throughout their history.




OPPOSITE DIRECTIONS
The northwestward movement of the Pacific Plate and the southeastward movement of the North American Plate cause folds and fissures throughout the region.

Strike-Slip Fault
In this fault the relative movement of the plates is mainly horizontal, along the Earth's surface, parallel to the direction of the fracture but not parallel to the fault plane. Transform faults between plates are usually of this type. Rather than a single fracture, they are generally made up of a system of smaller fractures, slanted from a centerline and more or less parallel to each other. The system can be several miles wide.

Streambeds Diverted by Tectonic Movement


Through friction and surface cracking, a transform fault creates transverse faults and, at the same time, alters them with its movement. Rivers and streams distorted by the San Andreas fault have three characteristic forms: streambeds with tectonic displacement, diverted streambeds, and streambeds with an orientation that is nearly oblique to the fault.

1



Diverted Streambed
The stream changes course as a result of the break.

2



Displaced Streambed
The streambed looks "broken" along its fault line.



WEST COAST OF THE UNITED STATES

Length of California	770 miles (1,240 km)
Length of fault	800 miles (1,300 km)
Maximum width of fault	60 miles (100 km)
Greatest displacement (1906)	20 feet (6 m)

140 years

The average interval between major ruptures that have taken place along the fault. The interval can vary between 20 and 300 years.

Fatal Crack
The great San Andreas fault in the western United States is the backbone of a system of faults. Following the great earthquake that leveled San Francisco in 1906, this system has been studied more than any other on Earth. It is basically a horizontal transform fault that forms the boundary between the Pacific and North American tectonic

plates. The system contains many complex lesser faults, and it has a total length of 800 miles (1,300 km). If both plates were able to slide past each other smoothly, no earthquakes would result. However, the borders of the plates are in contact with each other. When the solid rock cannot withstand the growing strain, it breaks and unleashes an earthquake.

PAST AND FUTURE
Some 30 million years ago, the Peninsula of California was west of the present coast of Mexico. Thirty million years from now, it is possible that it may be some distance off the coast of Canada.

Volcanoes

MOUNT ETNA
With a height of 10,810 feet (3,295 m), Etna is the largest and most active volcano in Europe.

FLAMING FURNACE 26-27
CLASSIFICATION 28-29
FLASH OF FIRE 30-31
MOUNT ST. HELENS 32-33
KRAKATOA 34-35

AFTERMATH OF FURY 36-37
JETS OF WATER 38-39
RINGS OF CORAL 40-41
FROZEN FLAME 42-43



Mount Etna has always been an active volcano, as seen from the references to its activity that have been made throughout history. It

could be said that the volcano has not given the beautiful island of Sicily a moment's rest. The Greek philosopher Plato was the first to study Mount Etna. He traveled to Italy especially to see it





up close, and he subsequently described how the lava cooled. Today Etna's periodic eruptions continue to draw hundreds of thousands of tourists, who enjoy the spectacular fireworks

produced by its red-hot explosions. This phenomenon is visible from the entire east coast of Sicily because of the region's favorable weather conditions and the constant strong winds. ●

Flaming Furnace

Volcanoes are among the most powerful manifestations of our planet's dynamic interior. The magma they release at the Earth's surface can cause phenomena that devastate surrounding areas: explosions, enormous flows of molten rock, fire and ash that rain from the sky, floods, and mudslides. Since ancient times, human beings have feared volcanoes, even seeing their smoking craters as an entrance to the underworld. Every volcano has a life cycle, during which it can modify the topography and the climate and after which it becomes extinct. ■

LIFE AND DEATH OF A VOLCANO: THE FORMATION OF A CALDERA




INTRUSION OF MAGMA

PLUG OF AN EXTINCT VOLCANO

SILL
Layer of magma forms between rock layers.

DIKE
Vertical Channel of Magma.

ACTIVE VOLCANO



ERUPTION OF LAVA

CLOUD OF ASH

STREAMS OF LAVA
flow down the flanks of the volcano.

VOLCANIC CONE
Made of layers of igneous rock, formed from previous eruptions. Each lava flow adds a new layer.

MAIN CONDUIT
The pipe through which magma rises. It connects the magma chamber with the surface.

SEEPAGE OF GROUNDWATER


Magma can reach the surface, or it can stay below ground and exert pressure between the layers of rock. These seepages of magma have various names.

MAGMA CHAMBER
Mass of molten rock at temperatures that may exceed
2,000° F
(1,100° C)

In an active volcano, magma in the chamber is in constant motion because of fluctuations of temperature and pressure (convection currents).

MOUNTAIN-RANGE VOLCANOES

Many volcanoes are caused by phenomena occurring in subduction zones along convergent plate boundaries.



CRATER
Depression or hollow from which eruptions expel magmatic materials (lava, gas, steam, ash, etc.)


PARASITIC VOLCANO
Composite volcanic cones have more than one crater.

SECONDARY CONDUIT

EXTINCT CONDUIT

UNDER THE VOLCANO

In its ascent to the surface, the magma may be blocked in various chambers at different levels of the lithosphere.



Classification

No two volcanoes on Earth are exactly alike, although they have characteristics that permit them to be studied according to six basic types: shield volcanoes, cinder cones, stratovolcanoes, lava cones, fissure volcanoes, and calderas. A volcano's shape depends on its origin, how the eruption began, processes that accompany the volcanic activity, and the degree of danger the volcano poses to life in surrounding areas. ●

THE MOST COMMON

Stratovolcanoes, or composite cones, are strung along the edges of the Pacific Plate in the region known as the "Ring of Fire."

LAVA DOME

The sides are formed by the accumulation of "hard" lava, made viscous by its high silicon content. Instead of flowing, it quickly hardens in place.

CINDER CONE

Cone-shaped, circular mounds up to 980 feet (300 m) high. They are formed when falling debris or ash accumulates near the crater. These volcanic cones have gently sloping sides, with an angle between 30° and 40°.


SHIELD VOLCANO

The diameter of these volcanoes is much greater than their height. They are formed by the accumulation of highly fluid lava flows, so they are low, with gently sloping sides, and they are nearly flat on top.

STRATOVOLCANO (COMPOSITE VOLCANO)

Nearly symmetrical in appearance, formed by layers of fragmented material (ash and pyroclasts) between lava flows. A stratovolcano is structured around a main conduit, although it may also have several branch pipes. This is usually the most violent type of volcano.

IGNEOUS INTRUSIONS: A PECULIAR PROFILE




CHAPEL OF ST. MICHAEL

Built in Le Puy, France, on top of a volcanic neck of hard rock that once sealed the conduit of a volcano. The volcano's cone has long since been worn away by erosion; the lava plug remains.

262

FEET (80 M)
The height of the plug, from base to peak.



MOUNT ILAMATEPEC

Cinder cone located 45 miles (65 km) west of the capital of El Salvador. Its last recorded eruption was in October 2005.



MOUNT KILAUEA

Shield volcano in Hawaii. One of the most active shield volcanoes on Earth.



MOUNT FUJI

Composite volcano 12,400 feet (3,776 m) high, the highest in Japan. Its last eruption was in 1707.



CALDERA BLANCA

Located on Lanzarote, Canary Islands, in the fissure zone known as the Montañas de Fuego (Fire Mountains).



MAUNA ULU

Fissure volcano, about 5 miles (8 km) from the top of Kilauea (Hawaii). This is one of the most active volcanoes in the central Pacific.



Flash of Fire

A volcanic eruption is a process that can last from a few hours to several decades. Some are devastating, but others are mild. The severity of the eruption depends on the dynamics between the magma, dissolved gas, and rocks within the volcano. The most potent explosions often result from thousands of years of accumulation of magma and gas, as pressure builds up inside the chamber. Other volcanoes, such as Stromboli and Etna, reach an explosive point every few months and have frequent emissions.


HOW IT HAPPENS

3. **THE ESCAPE**

When the mounting pressure of the magma becomes greater than the materials between the magma and the floor of the volcano's crater can bear, these materials are ejected.
2. **IN THE CONDUIT**

A solid layer of fragmented materials blocks the magma that contains the volatile gases. As the magma rises and mixes with volatile gases and water vapor, the pockets of gases and steam that form give the magma its explosive power.
1. **IN THE CHAMBER**

There is a level at which liquefaction takes place and at which rising magma, under pressure, mixes with gases in the ground. The rising currents of magma increase the pressure, hastening the mixing.



4. **PYROCLASTIC PRODUCTS**

In addition to lava, an eruption can eject solid materials called pyroclasts. Volcanic ash consists of pyroclastic material less than 0.08 inch (2 mm) in size. An explosion can even expel granite blocks.


BOMB	2.5 inches (64 mm) and up
LAPILLI	0.08 to 2.5 inches (2 mm to 64 mm)
ASH	Up to 0.08 inch (2 mm)

5. **LAVA FLOWS**

On the volcanic island of Hawaii, nonerupting flows of lava abound. Local terms for lava include "aa," viscous lava flows that sweep away sediments, and "pahoehoe," more fluid lava that solidifies in soft waves.


EFFUSIVE ACTIVITY

Mild eruptions with a low frequency of explosions. The lava has a low gas content, and it flows out of openings and fissures.



EXPLOSIVE ACTIVITY

Comes from the combination of high levels of gas with relatively viscous lava, which can produce pyroclasts and build up great pressure. Different types of explosions are distinguished based on their size and volume. The greatest explosions can raise ash into a column several miles high.



LAVA FLOW MT. KILAUEA, HAWAII



TYPES OF EFFUSIVE ERUPTION

Dome Low, like a shield volcano, with a single opening.

Fissure Often several miles long.

Lava Seeps out slowly.

HAWAIIAN

Volcanoes such as Mauna Loa and Kilauea expel large amounts of basaltic lava with a low gas content, so their eruptions are very mild. They sometimes emit vertical streams of bright lava ("fountains of fire") that can reach up to 330 feet (100 m) in height.

FISSURE

Typical in ocean rift zones, fissures are also found on the sides of composite cones such as Etna (Italy) or near shield volcanoes (Hawaii). The greatest eruption of this type was that of Laki, Iceland, in 1783: 2.9 cubic miles (12 cu km) of lava was expelled from a crack 16 miles (25 km) long.

TYPES OF EXPLOSIVE ERUPTION

Cloud of burning material from about 330 to 3,300 feet (100-1,000 m) high.

The column can reach a height of 49,000 feet (15 km).

Cloud can reach above 82,000 feet (25 km).

Burning cloud moving down the slope.

STROMBOLIAN

The volcano Stromboli in Sicily, Italy, gave its name to these high-frequency eruptions. The relatively low volume of expelled pyroclasts allows these eruptions to occur approximately every five years.

VULCANIAN

Named after Vulcano in Sicily. As eruptions eject more material and become more explosive, they become less frequent. The 1985 eruption of Nevado del Ruiz expelled tens of thousands of cubic yards of lava and ash.


VESUVIAN

Also called Plinian, the most violent explosions raise columns of smoke and ash that can reach into the stratosphere and last up to two years, as in the case of Krakatoa (1883).

PELEAN

A plug of lava blocks the crater and diverts the column to one side after a large explosion. As with Mt. Pelée in 1902, the pyroclastic flow and lava are violently expelled down the slope in a burning cloud that sweeps away everything in its path.

LAKE OF LAVA MAKA-O-PUHL, HAWAII



COOLED LAVA (PAHOEHOE) MT. KILAUEA, HAWAII




FROM OUTER SPACE

A photo of the eruption of Mt. Augustine in Alaska, taken by the Landsat 5 satellite hours after the March 27, 1986, eruption.

SMOKE COLUMN

7 Miles
(11.5 Km) HIGH



Mount St. Helens

Within the territory of the United States, active volcanoes are not limited to exotic regions such as Alaska or Hawaii. One of the most explosive volcanoes in North America is in Washington state. Mount St. Helens, after a long period of calm, had an eruption of ash and vapor on May 18, 1980. The effects were devastating: 57 people were killed, and lava flows destroyed trees over an area of 232 square miles (600 sq km). The lake overflowed, causing mudslides that destroyed houses and roads. The area will need a century to recover.

9,680 feet
(2,950 m)

-1,315 feet
(-401 m)

In the eruption Mount St. Helens lost its conical stratovolcano shape and became a caldera.



BEFORE THE ERUPTION
The symmetrical cone, surrounded by forest and prairies, was admired as the American Fuji. The eruption left a horseshoe-shaped caldera, surrounded by devastation.

DURING THE EXPLOSION
The energy released was the equivalent of 500 nuclear bombs. The top of the mountain flew off like the cap of a shaken bottle of soda.

232 SQUARE MILES
600 sq km

SURFACE DESTRUCTION
The effects were devastating: 250 houses, 47 bridges, rail lines, and 190 miles (300 km) of highway were lost.

8 miles
13 km

Pulverized and incinerated by the force of the lava and the pyroclastic flow. Temperatures rose above 1,110° F (600° C).

15 miles
24 km

Range of the shock wave from the pyroclastic flow. The heat and ash left acres of forest completely destroyed.

The Forest
Burned trees covered with ash, several miles from the volcano

Cork Top
Like the cork in a bottle of champagne, the top of the mountain burst off because of pressure from the magma.

OLYMPIA WASHINGTON STATE




Type of Volcano	Stratovolcano
Size of Base	5.9 mi (9.5 km)
Type of Activity	Explosive
Type of Eruption	Plinian
Most Recent Eruptions	1980, 1998, 2004
Fatalities	57

Warning Signs

Two months before the great explosion, Mount St. Helens gave several warning signs: a series of seismic movements, small explosions, and a swelling of the mountain's north slope, caused by magma rising toward the surface. Finally on May 18, an earthquake caused a landslide that carried away the top of the volcano. Later, several collapses at the base of the column caused numerous pyroclastic flows with temperatures of nearly 1,300° F (700° C).


1. 00:00

SWELLING
The uninterrupted flow of magma toward the volcano's surface caused the north slope of the mountain to swell, and later collapse in an avalanche.




2. 00:40

PRESSURE ON THE NORTH SLOPE
The swelling of the mountain was no doubt caused by the first eruption, almost two months before the final explosion.




3. 00:50

INITIAL ERUPTIONS
The north slope gave way to the great pressure of the magma in an explosive eruption. The lava traveled 16 miles (25 km) at 246 feet (75 m) per second.



4. 00:60

EXPLOSION AND VERTICAL COLLAPSE
At the foot of the volcano, a valley 640 feet (195 m) deep was buried in volcanic material. Over 10 million trees were destroyed.




Krakatoa

In early 1883, Krakatoa was just one of many volcanic islands on Earth. It was located in the Straits of Sunda, between Java and Sumatra in the Dutch East Indies, now known as Indonesia. It had an area of 10.8 square miles (28 sq km) and a central peak with a height of 2,690 feet (820 m). In August 1883, the volcano exploded, and the island was shattered in the largest natural explosion in history. ●

The Island That Exploded

■ Krakatoa was near the subduction zone between the Indo-Australian and Eurasian plates. The island's inhabitants were unconcerned about the volcano because the most recent previous eruption had been in 1681. Some even thought the

volcano was extinct. On the morning of Aug. 27, 1883, the island exploded. The explosion was heard as far away as Madagascar. The sky was darkened, and the tsunamis that followed the explosion were up to 130 feet (40 m) high.




1 BEFORE
In May the volcano began showing signs in the form of small quakes and spouting vapor, smoke, and ash. None of this served to warn of the terrible explosion to come, and some even took trips to see the volcano's "pyrotechnics."

2 DURING
At 5:30 a.m. the island burst from the accumulated pressure, opening a crater 820 feet (250 m) deep. Water immediately rushed in, causing a gigantic tsunami.

**130 feet
(40 m)**

The height of the tsunami waves, which traveled at 700 miles per hour (1,120 km/h).



**34
miles
(55 km)**

The height of the column of ash.



KRAKATOA

Latitude 6° 06' S
Longitude 105° 25' E

Surface Area	10.8 square miles (28 sq km)
Remaining Surface Area	3 square miles (8 sq km)
Range of the Explosion	2,900 miles (4,600 km)
Range of Debris	1,550 miles (2,500 km)
Tsunami Victims	36,000


PYROCLASTICS

The pyroclastic flows were so violent that, according to the descriptions of sailors, they reached up to 37 miles (80 km) from the island.



500

MEGATONS
The energy released, equivalent to 25,000 atomic bombs such as the one dropped on Hiroshima.



3

AFTER

A crater nearly 4 miles (6.4 km) in diameter was left where the volcano had been. About 1927, new volcanic activity was observed in the area. In 1930, a cone emerged. Anak Krakatoa ("daughter of Krakatoa") appeared in 1952; it grows at a rate of nearly 15 feet (4.5 m) per year.

FRACTION

Two thirds of the island was destroyed, and only a part of Rakata survived the explosion.


Aftereffects

■ The ash released into the atmosphere left enough particles suspended in the air to give the Moon a blue tinge for years afterward. The Earth's average temperature also decreased.

Long-Term Effects

WATER LEVEL

The water level fluctuated as far away as the English Channel.



PRESSURE WAVE

The atmospheric pressure wave went around the world seven times.

Atmosphere

The ash expelled by the explosion lingered for years

Aftermath of Fury

When a volcano becomes active and explodes, it sets in motion a chain of events beyond the mere danger of the burning lava that flows down its slopes. Gas and ash are expelled into the atmosphere and affect the local climate. At times they interfere with the global climate, with more devastating effects. The overflow of lakes can also cause mudslides called lahars, which bury whole cities. In coastal areas, lahars can cause tsunamis. ●

LAVA FLOWS

In volcanoes with calderas, low-viscosity lava can flow without erupting, as with the Laki fissures in 1783. Low-viscosity lava drips with the consistency of clear honey. Viscous lava is thick and sticky, like crystallized honey.

LAVA IN VOLCANO NATIONAL PARK, HAWAII

CINDER CONE

Cone with walls of hardened lava.



As the lava flows upward, the cone explodes.



MOLDS OF TREES

Burned tree underneath cooled lava.



The petrified mold forms a minivolcano.



LAVA TUBES

Outer layer of hardened lava.



Inside, the lava stays hot and fluid.



RESCUE IN ARMERO, COLOMBIA

Mudslide after the eruption of the volcano Nevado del Ruiz. A rescue worker helps a boy trapped in a lahar.



MUDSLIDES OR LAHARS

Rain mixed with snow and melted by the heat, along with tremors and overflowing lakes, can cause mudslides called "lahars." These can be even more destructive than the eruption itself, destroying everything in their path as they flow downhill. They occur frequently on high volcanoes that have glaciers on their summit.

ARMERO FROM ABOVE

On Nov. 13, 1985, the city of Armero, Colombia, was devastated by mudslides from the eruption of the volcano Nevado del Ruiz.




PYROCLASTIC FLOW

Incandescent masses of ash, gas, and rock fragments that come from sudden explosive eruptions flow downhill at high temperature, burning and sweeping away everything in their path.

SPEED
61-132 miles per hour
(100-200 km/h)

TEMPERATURE
930-1830° F
(500-1000° C)

RANGE
30-61 miles per hour
(50-100 km/h)
In rhyolitic eruptions.



DEADLY FLOW

A bird caught in the eruption of Mount St. Helens, which devastated forests up to a distance of about 8 miles (13 km). The heat and ash left many acres completely destroyed.



AFTEREFFECTS



OPTICAL EFFECTS


Particles of volcanic ash intensify yellow and red colors. After the eruption of Tambora in Indonesia in 1815, unusually colorful sunrises were seen worldwide.

GRAPHICAL RECONSTRUCTION

Aerial photo of a small fishing village on San Vicente Island, covered in volcanic ash. This eruption had no victims.

QUAKES

The underground action of magma and gas creates pressure that, in turn, causes movement in the Earth's crust. The quakes can be warning signs of an impending eruption.



Jets of Water

Geysers are intermittent spurts of hot water that can shoot up dozens of yards into the sky. Geysers form in the few regions of the planet with favorable hydrogeology, where the energy of past volcanic activity has left water trapped in subterranean rocks. Days or weeks may pass between eruptions. Most of these spectacular phenomena are found in Yellowstone National Park (U.S.) and in northern New Zealand.

The eruptive cycle

5. THE CYCLE REPEATS
When the water pressure in the chambers is relieved, the spurt of water abates, and the cycle repeats. Water builds up again in cracks of the rock and in permeable layers.


On average, a geyser can expel up to **7,900 gallons** (30,000 l) of water

4. SPURTING SPRAY
The water spurts out of the cone at irregular intervals. The lapse between spurts depends on the time it takes for the chambers to fill up with water, come to a boil, and produce steam.

The average height reached of the spurt of water is about **148 feet** (45 m)

3. BURSTING FORTH
The water rises by convection and spurts out the main vent to the chimney or cone. The deepest water becomes steam and explodes outward.

CONVECTION FORCES
This is a phenomenon equivalent to boiling water.



2. MOUNTING PRESSURE
The underground chambers fill with water, steam, and gas at high temperatures, and these are then expelled through secondary conduits to the main vent.

1. HEATED WATER
Thousands of years after the eruption of a volcano, the area beneath it is still hot. The heat rising from the magma chambers warms water that filters down from the soil. In the subsoil, the water can reach temperatures of up to 518° F (270° C), but pressure from cooler water above keeps it from boiling.

Temperatures up to **194°F** (90° C)

MORPHOLOGY OF THE CHAMBERS
The heat of a magma chamber warms water in the cavity. The chamber fills, and the water rises to the surface. The pressure in the cavity is released, and the water suddenly boils and spurts out.



Geyser with multiple chambers

HEAT SOURCE
Magma between 2 and 6 miles (3-10 km) deep, at 930-1,110° F (500-600° C).


PRINCIPAL GEOTHERMAL FIELDS

There are some 1,000 geysers worldwide, and 50 percent are in Yellowstone National Park (U.S.).



GRAND PRISMATIC SPRING
This spring, in Yellowstone National Park, is the largest hot spring in the United States and the third largest in the world. It measures 246 by 377 feet (75 by 115 m), and it emits about 530 gallons (2,000 l) of water per minute. It has a unique color: red mixed with yellow and green.

DISCHARGE
530 gallons (2,000 l) OF WATER PER MINUTE




RECORD HEIGHT
In 1904, New Zealand's Waimangu geyser (now inactive) emitted a record-setting spurt of water. In 1903, four tourists lost their lives when they unknowingly came too close to the geyser.

1,450 ft (442 m) **1,500 ft** (457 m)
TALLEST U.S. BUILDING **RECORD HEIGHT**

OTHER POSTVOLCANIC ACTIVITY


FUMAROLE
This is a place where there is a constant emission of water vapor because the temperature of the magma is above 212° F (100° C).



SOLFATARA
The thermal layers emit sulfur and sulfurous anhydride.



MUD BASIN
These basins produce their own mud; sulfuric acid corrodes the rocks on the surface and creates a mud-filled hollow.



MINERAL SPRINGS

Their water contains many minerals, known since antiquity for their curative properties. Among other substances, they include sodium, potassium, calcium, magnesium, silicon oxide, chlorine, sulfates (SO₄), and carbonates (HCO₃). They are very helpful for rheumatic illnesses.


Steam Energy
In Iceland, geothermic steam is used not only in thermal spas but also to power turbines that generate most of the country's electricity.

Rings of Coral

In the middle of the ocean, in the tropics, there are round, ring-shaped islands called atolls. They are formed from coral reefs that grew along the sides of ancient volcanoes that are now submerged. As the coral grows, it forms a barrier of reefs that surround the island like a fort. How does the process work? Gradually, volcanic islands sink, and the reefs around them form a barrier. Finally, the volcano is completely submerged; no longer visible, it is replaced by an atoll. ●

FORMATION OF AN ATOLL


1. THE BEGINNING OF AN ATOLL. The undersea flanks of an extinct volcano are colonized by corals, which continue to grow.



2. THE CORALS GAIN GROUND. As the surrounding reef settles and continues to expand, it becomes a barrier reef that surrounds the summit of the ancient volcano, now inactive.




3. THE ATOLL SOLIDIFIES. Eventually the island will be completely covered and will sink below the water, leaving a ring of growing coral with a shallow lagoon in the middle.




WHAT ARE CORALS?

Corals are formed from the exoskeletons of a group of Cnidarian species. These marine invertebrates have a sexual phase, called a medusa, and an asexual phase, called a polyp. The polyps secrete an outer skeleton composed of calcium carbonate, and they live in symbiosis with one-celled algae.

HARD CORAL POLYP



BRANCHING CORAL



COMPACT CORAL

Original polyp formation (dead)
Layer of live polyps

ATOLLS AND VOLCANIC ISLANDS AROUND THE WORLD

Coral reefs are found in the world's oceans, usually between the Tropic of Cancer and the Tropic of Capricorn.



OPTIMAL CONDITIONS


Coral is mainly found in the photic zone (less than 165 feet [50 m] deep), where sunlight reaches the bottom and provides sufficient energy. For reefs to grow, the water temperature should be between **68° and 82° F** (20-28° C).




Scale in miles (km)
0 (0) 0.6 (1)
0.3 (0.5)

Country	Republic of Kiribati
Ocean	North Pacific
Archipelago	Gilbert Islands
Surface area	10.8 square miles (28 sq km)
Altitude	6.9 ft (2.1 m)
LEGEND	● Town ★ Capital

HAWAIIAN ARCHIPELAGO



FORMATION OF A VOLCANIC ISLAND



Molokai	Kahoolawe	Lanai	Maui	Hawaii
1,476 ft (450 m)	3,369 ft (1,027 m)	3,369 ft (1,027 m)	10,023 ft (3,055 m)	13,799 ft (4,206 m)

Frozen Flame

It is known as the land of ice and fire. Under Iceland's frozen surface there smolders a volcanic fire that at times breaks free and causes disasters. The island is located over a hot spot on the Central Atlantic Ridge. In this area the ocean bed is expanding, and large quantities of lava flow from vents, fissures, and craters. ●



ICELAND

Latitude 64° 6' N
Longitude -21° 54' E


Surface Area	39,768 sq miles (103,000 sq km)
Population	293,577
Population density	1 per sq mile (2.8 per sq km)
Area of lakes	1,064 sq miles (2,757 sq km)
Glaciers	4,603 sq miles (11,922 sq km)

ENERGY

The islanders use geothermal (steam) energy from volcanoes and geysers for heat, hot water, and electric energy.

Split Down the Middle

Part of Iceland rests on the North American Plate, which is drifting westward. The rest of Iceland is on the Eurasian Plate, drifting eastward. As tectonic forces pull on the plates, the island is slowly splitting in two and forming a fault. The edges of the two plates are marked by gorges and cliffs. Thus, the ocean bed is growing at the surface.



REYKJAVIK


The capital of Iceland is the northernmost capital in the world.

Birth of an Island

On Nov. 15, 1963, an undersea volcanic eruption off the southern coast of Iceland gave rise to the island of Surtsey, the newest landmass on the planet. The eruption began with a large column of ash and smoke. Later, heat and pressure deep within the Earth pushed part of the Mid-Atlantic Ridge to the surface. The island kept growing for several months, and today it has a surface area of 1.0 square mile (2.6 sq km). The island was named after Surtur, a fire giant from Icelandic mythology.

1/5

of all the lava that has emerged on the Earth's surface since 1500 has come from Iceland.



RIFT ZONE

If the rift zone that crosses the island from southwest to north were cut in two, different ages of the Earth would be revealed according to the segment being analyzed. For example, the rock 60 miles (100 km) from the rift is six million years old.

KRAFLA VOLCANIC CRATER

This volcano has been very active throughout history. Of its 29 active periods, the most recent was in 1984.



Crater of 1,640 feet (500 m). The caldera measures 6 miles (10 km) across.

Lake Viti (Hell in Icelandic); Krafla Volcano

hot spot

KRAFLA

Lake Myvatn

FREMRINAM

ASKJA

HOFSTJOKUL

BARDARBUNGA

GRIMSVÖTN

LAKI

The largest eruption of lava in history occurred in 1783; the ashes reached China.

HEKLA

Its largest eruption was in 1104.

TINDFJALL

KATLA

VESTMANNA

GLACIAL CAP OF VATNAJÖKULL

ERUPTION UNDER THE ICE

In 1996 a fissure opened up between Grimsvötn and Bardarbunga. The lava made a hole 590 feet (180 m) deep in the ice and released a column of ash and steam. The eruption lasted 13 days.



1 The first eruptions were caused by the interaction of magma and water. The explosions were infrequent, and rocks were thrown only a few yards from the volcano.



2 Repeated eruptions expelled vapor and ash into the air, forming a column over 6 miles (10 km) high. The island was formed from volcanic blocks and masses of lava.



3 The entire process lasted three-and-a-half years. Over 0.25 cubic mile (1 cu km) of lava and ash was expelled, with only 9 percent of it appearing above sea level.

Study and Prevention



INCANDESCENT ROCK
A river of lava from Mt. Kilauea flows constantly, forming surface wrinkles that deform under the lightest step.

LATENT DANGER 46-47

LEARN MORE 48-49

PREPARATIONS FOR DISASTER 50-51

BURIED IN A DAY 52-55

ERUPTIONS THROUGH TIME 56-57

Large eruptions often give warning signs months in advance. These signs consist of any observable manifestation on the exterior of the Earth's



crust. They may include emissions of steam, gases, or ash and rising temperatures in the lake that typically forms in the crater. This is why volcanic seismology is

considered one of the most useful tools for protecting nearby towns. Several seismic recording stations are typically placed around the cone of an active volcano. Among other things,

the readings scientists get give them a clear view of the varying depths of the volcano's tremors-extremely important data for estimating the probability of a major eruption. ●

Latent Danger

Some locations have a greater propensity for volcanic activity. Most of these areas are found where tectonic plates meet, whether they are approaching or moving away from each other. The largest concentration of volcanoes is found in a region of the Pacific known as the "Ring of Fire." Volcanoes are also found in the Mediterranean Sea, in Africa, and in the Atlantic Ocean. ●




Increasing Knowledge


Volcanology is the scientific study of volcanoes. Volcanologists study eruptions from airplanes and satellites, and they film volcanic activity from far off. However, to study the inner workings of a volcano up close, they must scale near-vertical cliffs and face the dangers of lava, gas, and mudslides. Only then can they take samples and set up equipment to detect tremors and sounds. ●

Field Measurements


Monitoring a volcano includes gathering and analyzing samples and measuring various phenomena. Seismic movements, varying compositions of gases, deformations in the rock, and changes in electromagnetic fields induced by the movement of underground magma can all provide clues to predict volcanic activity.




LAVA TEMPERATURE
is measured with a thermometer called a Thermopar; glass thermometers would melt from the heat. Temperatures of water and of nearby rocks are other variables to take into account.



TILTOMETERS
These are placed on the slopes of a volcano to record soil changes that precede an eruption. Points are determined (A-B) to monitor how pressure from the magma deforms the surface between them.




GLOBAL POSITIONING SYSTEM (GPS)
Movements in the magma cause hundreds of cracks in the cone. A GPS system records images continuously and analyzes the deformation over a period of time.




TEMBLORS OR EARTHQUAKES
Portable seismographs are used to detect movements in the ground within 6 miles (10 km) of the volcano that is being studied. These tremors can give clues about the movements of the magma.



THE SIZE OF THE CRATER
The widening of the crater caused by volcanic activity and the growth of the solid lava domes are measured. This growth implies certain risks for the proximity of an eruption.



HYDROLOGICAL MONITORING
Mudslides, or lahars, can bury large areas. Monitoring the volume of water in the area makes it possible to alert and evacuate the population when the amount of water passes critical points.



LAVA COLLECTION
The study of lava can determine its mineral composition and its origin. Lava deposits are also analyzed because the history of a volcano's eruptions can give clues about a future eruption.

SAMPLING OF VOLCANIC GASES
Gas and water vapor dissolved in magma provides the energy that powers eruptions. Visible emissions, such as sulfur and steam, are measured, as are invisible gases. Analyzing the gases' composition makes it possible to predict the beginning and end of an eruption.

GAS MASK

VACUUM TUBE

TITANIUM TUBE

GAS ESCAPING FROM CRACK

Volcanologists Taking Gas Samples from a Fumarole on Lipari Island, Italy

Preparations for Disaster

Volcanic eruptions are dangerous to surrounding populations for two basic reasons. One danger is posed by the volcanic material that flows down the sides of the volcano (lava flows and mudslides), and the other danger is from the volcano's pyroclastic material, especially ash. Ash fallout can bury entire cities. Experts have developed an effective series of prevention and safety measures for people living in volcanic areas. These measures greatly reduce the highest risks. ●

Before an Eruption

It is best to get informed about safety measures, evacuation routes, safe areas, and alarm systems before a volcanic eruption. Other safety measures include stocking up on nonperishable food, obtaining gas masks and potable water, and checking the load-bearing capacity of roofs.

Do not carry more than
44 pounds
(20 kg) OF PROVISIONS.

Evacuation of Nearby Areas

In the immediate area (within 12 miles [20 km]) of the volcano, evacuation is the only possible safety measure. Returning home will be possible only when permission is given. Keep in mind that it takes a long time for life to return to normal after an evacuation.



MEDICAL PRECAUTIONS

Keep a first-aid kit and essential medications on hand, and keep vaccinations up to date.



PROVISIONS

Water and food are indispensable, especially if you evacuate the area on your own.



SHUT OFF UTILITIES

Before leaving a house, shut off the electricity, gas, and water. Tape doors and windows shut.



CIVIL DEFENSE

Follow all recommendations, be alert to official information, and do not spread rumors.

RIVERS AND STREAMS

Large volumes of water pose a threat of mudslides. Avoid these areas.

12 miles
(20 km)

BRIDGES

When possible, do not use for your evacuation route because they might collapse.

HIGHER ELEVATIONS

These are the preferred sites for evacuations from volcanic eruptions. High ground is safe from lahars and lava flows, and if there is shelter there, it is also safe from rains of ash.

Areas of Falling Ash

Most of the population lives outside the volcano's range, but ash from an eruption can become highly volatile and fall over wide areas. Wind can carry ash to other areas, so the best preventive efforts are focused on warning people about what to do in case of falling ash.

AT HOME

It is best to stay indoors during an ashfall. One of the main precautions is to provide for potable drinking water, because the usual water supply will be interrupted because of pollution risks, especially if the water supply comes from lakes or rivers in the area.

AVOID DRIVING

If you must drive, do so slowly and turn on your headlights. It is best to leave the car parked in an enclosed space or under cover.

LAHARS AND PYROCLASTIC FLOWS

Lahars (mudflows) can form from rainwater or melting snow. Volcanic danger zones often have strategies to divert rivers and reduce the volume of water in dams and reservoirs.

12 miles
(20 km)

Considered to be the critical distance from a volcano in emergency relief efforts.

WIND AND RAIN

Wind is a risk factor that spreads volatile ash over a large area so that settlements at a distance greater than 60 miles (100 km) can be affected. The greatest danger posed by falling ash is that it can mix with rain falling on the roofs of houses and form a heavy mass that will collapse the buildings.

60 miles
(100 km)

ALTERNATIVE ROUTES

Roads running through higher elevations are preferred because they cannot be reached by lava and mudflows.

WATER TANK

Roof-mounted water tanks should be disconnected and covered until the roof has been cleared of ashes.

ASH ON THE ROOF

Ash should be removed immediately (before it rains) so the roof does not collapse.

DOORS AND WINDOWS

It is best to always leave doors and windows shut tightly, as airtight as possible, for as long as the ashfall continues.

STAY CALM

To breathe, cover your face with a handkerchief soaked in water and vinegar.

DO NOT WASH WITH WATER

After the ashfall, washing with water will form a sticky and heavy paste that will be very hard to remove.

INFORMATION

Listen to the radio at all times.

CHILDREN

If children are at school, do not go to pick them up; they will be safe there.

AIR CONDITIONING

Air conditioners and large clothes dryers should not be used during an eruption.

MASKS

Use masks and special ash-protective clothing when outdoors.

Buried in One Day

At noon on Aug. 24, AD 79, Mount Vesuvius erupted near the coast of Naples Bay. The Roman cities of Pompeii and Herculaneum were completely buried in ashes and pyroclasts, in what would become one of the worst natural tragedies of ancient times. Many details from that day have reached us thanks to the narrative of Pliny the Younger. His well-known description of the eruption column as “shaped like a pine” caused this type of eruption to be named after him: a “Plinian eruption.”

10 A.M.

1 AN ALMOST NORMAL DAY

Tremors and earthquakes had been felt in the city for four days. Hanging lamps swayed, furniture moved, and some door frames had even cracked. Because these things happened about once a year

without any consequences, the inhabitants of Pompeii continued with their normal lives. The public forum was filled with people. The festivities of Isis were celebrated in the temple of Apollo.

POMPEII'S FORUM

This was the political, religious, and commercial heart of the city. Every day the forum was alive with Pompeii's citizens, as it was on August 24.

RICHES

Several precious objects such as this gold bracelet have been unearthed.

2

THE ERUPTION.

Suddenly Vesuvius spewed out a huge column of smoke, lava, and ash that formed a pyroclastic flow moving toward Pompeii. People ran in all directions seeking refuge in houses. The roughness of the sea made escape by water impossible.

1 P.M.

23 feet
(7 m)

The maximum depth of the ashes.

The Violent Awakening

Mount Vesuvius had been inactive for more than 800 years, until the pressure that had accumulated inside produced its explosion in the year 79. Most of the deaths during this tragedy were originally blamed on the ash that buried parts of the neighboring settlements (Herculaneum and Stabiae, as well as Pompeii). Now, though, the eruption is believed to have produced the typical “burning clouds” of a Plinian eruption: Flames of incandescent ash and gases were expelled at high speeds by the eruptive pressure. Suspended moist particles charged the air with electricity, causing an intense electric storm, whose flashes of lightning would have been the only source of light under the ashfall. Since then Vesuvius has had a dozen other important eruptions. The worst killed 4,000 people in 1631. The first volcanology observatory in the world was installed at Vesuvius in 1841.



POMPEII, ITALY

Latitude 40° 49' N
Longitude 14° 26' E

Distance from Vesuvius	6 miles (10 km)
Population in the year AD 79	20,000 people
Current population	27,000 people
Ash dispersion (79)	60 miles (100 km) (SE)
Last Eruption of Vesuvius	1944

9 P.M.

3

A TWO-DAY NIGHT

The tongues of lava from the volcano were seen better at night. The next morning the Sun's light could not be seen through the ash cloud. Pliny's narrative mentions a constant rain of

pyroclasts, continuing on the following morning, and emissions of sulfuric gases that killed many people. Many sought shelter on the beaches. Only on August 26 did the ashfall begin to disperse.

SEQUENCE OF THE ERUPTION

For more than 20 hours (the time the eruption lasted), the ash column rose and then fell on the surrounding area.

1

After the first explosion, the column of smoke began its vertical climb. The wind blew it toward the southeast.




2

The cloud spread nearly 60 miles (100 km) from side to side, and ash fell on the city for a whole day.



3

By 7:30 A.M. on August 25, the pyroclastic flows reached Pompeii. These flows are estimated to have reached temperatures of 1,022° F (550° C).



RAIN OF STONES

Moments after the eruption, incandescent pumice stones fell from the sky.

In the House of the Faun

Objects and human bodies were found under Pompeii's ashes, preserved in the position in which the disaster surprised them. These valuable testimonies to the past have made possible the reconstruction of daily life in ancient Rome. The House of the Faun was one of the most luxurious villas in Pompeii.

Slaves worked in the kitchens, and there were utensils similar to those we use today.

The funnel-shaped roofs were used to collect rainwater.

Clients seeking protection or favors were received in the atrium or central patio.

Slave couples could meet only in the gardens.

Tiles decorated with the flora and fauna of the Nile.

This merchant home was the largest in Pompeii, with 32,290 square feet (3,000 sq m).

Good Eating and Drinking

Romans were more than fond of feasts. A dinner for the whole family, which normally began at four in the afternoon, could last for more than four hours. Meals were sumptuous affairs, and no one left until completely satisfied. Pompeii's wine was famous throughout Rome. Kept in pitchers, it was always served watered down. The Romans sometimes added flavorings, commonly including honey and pepper.

BRONZE FAUN
The name given to the house is from this statue found in the villa's atrium. The faun was considered a wild deity, with the ability to predict the future.



As in That Moment

In 1709, some of Pompeii's artifacts were found buried under volcanic ash, and that started a treasure hunt. It was not until 1864, though, that reconstruction and conservation of materials began with the work of Giuseppe Fiorelli. The exhibits that are the most fascinating to people who visit Pompeii's ruins today (about two million people every year) are his reconstructions of the bodies.




In a Pompeii Bar

There were several types of food and drink establishments in Pompeii, from food vendors in the streets to luxury services. These food places served many different social purposes but acted primarily as places for businessmen to meet. They were run mostly by slaves, men as well as women.

THE THERMOPOLIUM
The typical bar had a long marble tabletop with embedded containers in which food could be kept warm.

200 was the approximate number of places of this type in the city.



Some of these houses were anterooms of brothels.

Wine was served in small cups called "carafes."

Food included large quantities of nuts, olives, bread, cheese, and onions.

There were frescoes on the walls showing obscene images and pictures of drunken customers.

1 THE CATASTROPHE

Several corpses were covered by volcanic ash, which had accumulated in layers and later hardened. The bodies had decomposed, but their forms were molded in the volcanic rock.

2 RECONSTRUCTION

The work of Fiorelli was to fill these natural "tombs" (ash molds) with plaster. When the plaster hardened, the surrounding layers of ash were removed, leaving the outlines or molds of the bodies.



3 THE FORM, UNTOUCHED

Making plaster casts allowed precise reconstructions of the people's postures at the time of the disaster, and we have been able to learn details such as the hairstyles and dress of these people. Animal forms and other organic objects have also been reconstructed. Today the use of resins and silicones makes it possible to obtain even greater detail.

Historic Eruptions

The lava falls and flows, sweeping away everything in its path. This happens in a slow, uninterrupted way, and the lava destroys entire cities, towns, and forests and claims thousands of human lives. One of the most famous examples was the eruption of Mount Vesuvius in AD 79, which wiped out two cities and two cultures, those of Pompeii and Herculaneum. In the 20th century, the eruption of Mount Pelée destroyed the city of Saint-Pierre in Martinique in a few minutes and instantly killed almost its entire population. Volcanic activity also seems to be closely related to changes in climate. ●

AD 79

MOUNT VESUVIUS Naples, Italy	
Volume of ejected ash in cubic feet (cu m)	141,000 (4,000)
Victims	2,200
Characteristics	Active

The cities of Pompeii and Herculaneum were destroyed in AD 79 when Mount Vesuvius erupted. Until that day, it was not known that the mountain was a volcano because it had been inactive for over 300 years. This was one of the first eruptions to be recorded: Pliny the Younger stated in one of his manuscripts that he had seen how the mountain exploded. He described the gas and ash cloud rising above Vesuvius and how thick, hot lava fell. Many people died because they inhaled the poisonous gases.

1783

LAKI VOLCANO Iceland	
Volume of ejected ash in cubic feet (cu m)	490 billion (14 billion)
Victims	10,000
Characteristics	Very active

In spite of the fact that the eruptions are related to conic forms, most of the volcanic material comes out through fractures in the crust, called "fissures." The fissure eruptions of Laki were the greatest in Iceland; they created more than 20 vents in a distance of 15 miles (25 km). The gases ruined grasslands and killed livestock. The subsequent famine took the lives of 10,000 people.

Volcanoes and Climate

There is a strongly supported theory that relates climate changes to volcanic eruptions. The idea of linking the two phenomena is based on the fact that explosive eruptions spew huge amounts of gases and fine particles high into the stratosphere, where they spread around the Earth and remain for years. The volcanic

material blocks a portion of solar radiation, reducing air temperatures around the world. Perhaps the most notable cold period related to volcanic activity was the one that followed the eruption of Tambora in 1815. Some areas of North America and Europe had an especially harsh winter.

KALAPANA. After the Kilauea volcano (Hawaii) erupted in 1991, a lava flow advanced on the city, covering everything in its path.

1815

TAMBORA VOLCANO Indonesia	
Volume of ejected ash in cubic feet (cu m)	100 billion (3 billion)
Victims	10,000
Characteristics	Stratovolcano

After giving off fumes for seven months, Tambora erupted, and the ensuing catastrophe was felt around the globe. The ash cloud expanded to more than

370 miles (600 km) away from the epicenter of the eruption, and it was so thick that it hid the Sun for two days. The ashfall covered an area of 193,051 square miles (500,000 sq km). It is considered to be the most destructive volcanic explosion that ever took place. More than 10,000 people died during the eruption, and 82,000 died of illness and starvation after the eruption.

1883

KRAKATOA VOLCANO Java, Indonesia	
Volume of ejected ash in cubic feet (cu m)	670 billion (19 billion)
Victims	36,000
Characteristics	Active

Even though Krakatoa began to announce its forthcoming eruption with clouds of vapor and smoke, these signs, instead of preventing a disaster, became a tourist attraction. When the explosion took place, it destroyed two thirds of the island. Stones shot from the volcano reached a height of 34 miles (55 km)-beyond the stratosphere. A crater 4 miles (6.4 km) in diameter opened a chasm 820 feet (250 m) deep. Land and islands were swept bare.

1902

MOUNT PELÉE Martinique, Antilles	
Volume of ejected ash in cubic feet (cu m)	No figures available
Victims	30,000
Characteristics	Stratovolcano

A burning cloud and a thick mass of ash and hot lava were shot from this small volcano that completely destroyed the port city of Saint-Pierre. Most striking is the fact that this destruction took place in only a few minutes. The energy released was so great that trees were uprooted. Almost the entire population died, and only three people survived, one of them because he was trapped in the city jail.

1973

ELDFELL VOLCANO Heimaey Islands, Iceland	
Volume of ejected ash in cubic feet (cu m)	No figures available
Victims	0
Characteristics	656 feet (200 m)

The lava advanced, and it appeared that it would take everything in its path. Volcanologists decided that Heimaey Island, south of Iceland, should be evacuated. But a physics professor proposed watering the lava with seawater to solidify or harden it. Forty-seven pumps were used, and, after three months and 6.5 million tons (6 million metric tons) of water, the lava was stopped, and the port was saved. The eruption began on January 23 and ended on June 28.

1980

MOUNT ST. HELENS State of Washington, U.S.	
Volume of ejected ash in cubic feet (cu m)	35 billion (1 billion)
Victims	57
Characteristics	Active

Also known as the Mount Fuji of the American continent. During the 1980 explosion, 1,315 feet (401 m) of the mountain's top gave way through a fault on its side. A few minutes after the volcano began its eruption, rivers of lava flowed down its sides, carrying away the trees, houses, and bridges in their path. The eruption destroyed whole forests, and the volcanic debris devastated entire communities.

1982

EL CHICHÓN VOLCANO Mexico	
Volume of ejected ash in cubic feet (cu m)	No figures available
Victims	2,000
Characteristics	Active

On Sunday, March 28, after 100 years of inactivity, this volcano became active again and unleashed an eruption on April 4. The eruption caused the deaths of about 2,000 people who lived in the surrounding area, and it destroyed nine settlements. It was the worst volcanic disaster in Mexico's history.

1944

MOUNT VESUVIUS Naples, Italy	
Volume of ejected ash in cubic feet (cu m)	No figures available
Victims	2,000
Characteristics	End of a cycle

With this last activity, the Vesuvius volcano ended the cycle of eruptions it began in 1631. This explosion, along with

the previous one in 1906, caused severe material damage. The eruptions were responsible for more than 2,000 deaths from avalanches and lava bombs. Additionally, the 1944 eruption took place during World War II and caused as much damage as the eruption at the beginning of the 20th century had, because it flooded Somma, Atrio de Cevallo, Massa, and San Sebastiano.

Earthquakes

LOMA PRIETA
On Oct. 18, 1989, an earthquake measuring 7.0 on the Richter scale, with its epicenter in Loma Prieta, 52 miles (85 km) south of San Francisco, caused great damage, including the collapse of a section of the Bay Bridge.

DEEP RUPTURE 60-61

ELASTIC WAVES 62-63

BURSTS OF ENERGY 64-65

MEASURING AN EARTHQUAKE 66-67

VIOLENT SEAS 68-69

AFTER THE CATASTROPHE 70-71

CAUSE AND EFFECT 72-73



Earthquakes shake the ground in all directions, even though the effects of a quake depend on the magnitude, depth, and distance from its point of

origin. Often the waves are so strong that the Earth buckles, causing the collapse of houses and buildings, as happened in Loma Prieta. In mountainous regions earthquakes

can be followed by landslides and mudslides, whereas in the oceans, tsunamis may form; these walls of water strike the coast with enough force to destroy whole

cities, as occurred in Indonesia in December 2004. Thailand recorded the highest number of tourist deaths, and 80 percent of tourist areas were destroyed. ●

Deep Rupture

Earthquakes take place because tectonic plates are in constant motion, and therefore they collide with, slide past, and in some cases even slip on top of each other. The Earth's crust does not give outward signs of all the movement within it. Rather energy builds up from these movements within its rocks until the tension is more than the rock can bear. At this point the energy is released at the weakest parts of the crust. This causes the ground to move suddenly, unleashing an earthquake. ●

1 FORESHOCK
Small tremor that can anticipate an earthquake by days or even years. It could be strong enough to move a parked car.

2 AFTERSHOCK
New seismic movement that can take place after an earthquake. At times it can be even more destructive than the earthquake itself.

EARTHQUAKES PER YEAR

MAGNITUDE	QUANTITY
8 or Greater	1
7 to 7.9	18
6 to 6.9	120
5 to 5.9	800
4 to 4.9	6,200
3 to 3.9	49,000

30 Seconds
The time lapse between each tremor of the Earth's crust

EPICENTER
Point on the Earth's surface located directly above the focus.

HYPOCENTER OR FOCUS
Point of rupture, where the disturbance originates. Can be up to 435 miles (700 km) below the surface.

SOUTHERN ALPS

ALPINE FAULT

SOUTH ISLAND

LAKE TEKAPO

3 EARTHQUAKE
The main movement or tremor lasts a few seconds, after which some alterations become visible in the terrain near the epicenter.



NEW ZEALAND
Latitude 42° S
Longitude 174° E

Surface area	103,737 square miles (268,680 sq km)
Population	4,137,000
Population density	35 people per square mile (13.63 people per sq km)
Earthquakes per year (>4.0)	60-100
Total earthquakes per year	14,000

Riverbeds follow a curved path because of movement along the fault line.

7.05

7.65 Richter

6.10

FAULT PLANE
Usually curves rather than following a straight line. This irregularity causes the tectonic plates to collide, which leads to earthquakes as the plates move.

SEISMIC WAVES
transmit the force of the earthquake over great distances in a characteristic back-and-forth movement. Their intensity decreases with distance.

FOLDS
These result from tension that accumulates between tectonic plates. Earthquakes release part of the tension energy generated by orogenic folds.


15 miles (25 km)

Average depth of the Earth's crust below the island.



ALPINE FAULT IN NEW ZEALAND
As seen in the cross-section, South Island is divided by a large fault that changes the direction of subduction, depending on the area. To the north the Pacific Plate is sinking under the Indo-Australian Plate at an average rate of 1.7 inches (4.4 cm) per year. To the south, the Indo-Australian Plate is sinking 1.4 inches (3.8 cm) per year under the Pacific Plate.

FUTURE DEFORMATION OF THE ISLAND




To the west there is a plain that has traveled nearly 310 miles (500 km) to the north in the past 20 million years.

Elastic Waves

Seismic energy is a wave phenomenon, similar to the effect of a stone dropped into a pool of water. Seismic waves radiate out in all directions from the earthquake's hypocenter, or focus. The waves travel faster through hard rock and more slowly through loose sediment and through water. The forces produced by these waves can be broken down into simpler wave types to study their effects.

Different Types of Waves

There are basically two types of waves: body waves and surface waves. The body waves travel inside the Earth and transmit foreshocks that have little destructive power. They are divided into primary (P) waves and secondary (S) waves. Surface waves travel only along the Earth's surface, but, because of the tremors they produce in all directions, they cause the most destruction.



3.7 miles per second (6 km/s)
Typical Speed of P Waves in the Crust.

P waves travel through all types of material, and the waves themselves move in the direction of travel.

Primary Waves

High-speed waves that travel in straight lines, compressing and stretching solids and liquids they pass through.

SPEED IN DIFFERENT MATERIALS

MATERIAL	Granite	Basalt	Limestone	Sandstone	Water
Wave speed in feet per second (m/s)	17,000 (5,200)	21,000 (6,400)	7,900 (2,400)	11,500 (3,500)	4,800 (1,450)

The ground is compressed and stretched by turns along the path of wave propagation.



Focus
Vibrations travel outward from the focus, shaking the rock.

2.2 miles per second (3.6 km/s)

S waves are 1.7 times as slow as P waves.

They travel only through solids. They cause splitting motions that do not affect liquids. Their direction of travel is perpendicular to the direction of travel.

Surface Waves

appear on the surface after the P and S waves reach the epicenter. Having a lower frequency, surface waves have a greater effect on solids, which makes them more destructive.

1.9 miles per second (3.2 km/s)
Speed of surface waves in the same medium.

These waves travel only along the surface, at 90 percent of the speed of S waves.

LOVE WAVES

These move like horizontal S waves, trapped at the surface, but they are somewhat slower and make cuts parallel to their direction.

The soil is moved to both sides.

RAYLEIGH WAVES

These waves spread with an up-and-down motion, similar to ocean waves, causing fractures perpendicular to their travel by stretching the ground.

The ground is moved in an elliptical pattern.

The soil is moved to both sides, perpendicular to the wave's path of motion.

Secondary Waves


Body waves that shake the rock up and down and side to side as they move.

SPEED IN DIFFERENT MATERIALS

MATERIAL	Granite	Basalt	Limestone	Sandstone
Wave speed in feet per second (m/s)	9,800 (3,000)	1,500 (3,200)	4,430 (1,350)	7,050 (2,150)

TRAJECTORY OF P AND S WAVES

The Earth's outer core acts as a barrier to S waves, blocking them from reaching any point that forms an angle greater than 105° from the epicenter. P waves are transmitted farther through the core, but they may be diverted later on. Thus they are detected at points that form an angle of greater than 140° from the epicenter.



Types of Earthquakes

Although earthquakes generally cause all types of waves, some kinds of waves may predominate. This fact leads to a classification that depends on whether vertical or horizontal vibration causes the most movement. The depth of the epicenter can also affect its destructiveness.

BASED ON TYPE OF MOVEMENT



Trepidatory
Located near the epicenter, where the vertical component of the movement is greater than the horizontal.


Oscillatory

When a wave reaches soft soil, the horizontal movement is amplified, and the movement is said to be oscillating.



BASED ON FOCUS DEPTH

Earthquakes originate at points between 3 and 430 miles (5 and 700 km) underground. Ninety percent originate in the first 62 miles (100 km). Those originating between 43 and 190 miles (70 and 300 km) are considered intermediate. Superficial earthquakes (often of higher magnitude) occur above that level, and deep-focus earthquakes occur below it.



Superficial 43 miles (70 km)
Intermediate 190 miles (300 km)
Deep focus 430 miles (700 km)



OAKLAND, CALIFORNIA

Latitude 37° 46' N
Longitude 122° 13' W

Surface area of state	156,100 square miles (404,298 sq km)
Range of Damages	68 miles (110 km)
State population	36,132,147
Earthquakes per year (>4.0)	15-20
Earthquake victims	63
Magnitude on Richter scale	71

Bursts of tension

Seismic energy can even be compared to the power of nuclear bombs. In addition, the interaction between seismic waves and soil materials also causes a series of physical phenomena that can intensify its destructive capacity. An example of such an effect occurred when a section of an interstate highway plummeted to the ground during the 1989 earthquake in Loma Prieta, California. ●

FACTORS THAT DETERMINE THE EFFECTS OF AN EARTHQUAKE

INTRINSIC
Magnitude
Type of wave
Depth


GEOLOGIC
Distance
Wave direction
Topography
Groundwater saturation

SOCIAL
Quality of construction
Preparedness of the population
Time of day

THE HIGHWAY

Each soil type responds differently to an earthquake. The figure shows how the same quake can produce waves of different strengths in different soils of different composition. The 0.86-mile (1.4-km) collapsed section of Interstate 880 was built on the mud of San Francisco Bay.

SEISMOGRAPH READOUT



4 = 1,000 tons

Magnitude Energy released by TNT

The energy released by an earthquake of magnitude 4 on the Richter scale is equal to the energy released by a low-power atomic bomb.



7 = 32 million tons

Magnitude Energy released by TNT

The energy released by an earthquake of magnitude 7 on the Richter scale, such as the 1995 earthquake in Hyogo-Ken Nanbu, Japan, is equal to the energy released by a high-powered thermonuclear bomb (32 megatons).




12 = 160 quadrillion tons

Magnitude Energy released by TNT


The energy released by a hypothetical earthquake of magnitude 12 on the Richter scale (the greatest known earthquake was 9.5) would be equal to the energy released if the Earth were to split in half.

Liquefaction


Seismic tremors apply a force to muddy or water-saturated soils, filling the empty spaces between grains of sand. Solid particles become suspended in the liquid, the soil loses its load-bearing capacity, and buildings sink as if the ground were quicksand. That displaces some of the water, which rises to the surface.



1 The soil is compact, even though it contains water.



2 During the earthquake, the water causes the solid particles to shake.



3 Solid structures sink, and water rises.

Measuring an Earthquake

Earthquakes can be measured in terms of force, duration, and location. Many scientific instruments and comparative scales have been developed to take these measurements. Seismographs measure all three parameters. The Richter scale describes the force or intensity of an earthquake. Naturally, the destruction caused by earthquakes can be measured in many other ways: numbers of people left injured, dead, or homeless, damage and reconstruction costs, government and business expenditures, insurance costs, school days lost, and in many more ways.



CHARLES RICHTER
American seismologist (1900-85) who developed the scale of magnitude that bears his name.



GIUSEPPE MERCALLI
Italian volcanologist (1850-1914) who developed the first scale for measuring the intensity of an earthquake.



EMS 98 SCALE
In use since 1998 throughout the European Union and other countries that use the protocol, including those of northern Africa. This scale describes the intensity of earthquakes in European contexts, where the most modern construction may be found side by side with ancient buildings. Earthquakes there can have widely varying effects. The scale has 12 points that combine magnitude readings with levels of destruction.


USE OF SCALES WORLDWIDE	
☐ Richter and Mercalli	☒ EMS

Intensity

Concept of the destruction caused by an earthquake.

Modified Mercalli Scale

Between 1883 and 1902, this Italian volcanologist developed a scale to measure the intensity of earthquakes. It originally had 10 points based on the observation of the effects of seismic activity; it was later modified to 12. The first few levels consist of barely perceptible sensations. The highest levels apply to the destruction of buildings. This scale is widely used to compare levels of damage among different regions and socioeconomic conditions.




Richter Scale

In 1935, seismologist Charles Richter designed a scale to measure the amplitude of the largest waves registered by seismographs. An important feature of this scale is that the levels increase exponentially. Each point on the scale represents 10 times the movement and 30 times the energy of the point below it. Tremors of magnitude 2 or less are not perceptible to humans. This scale is the most widely used in the world because it can be used to compare the strength of earthquakes apart from their effects.

Magnitude

The energy released in a seismic event.



- I
- II
- III
- IV
- V
- VI
- VII
- VIII
- IX
- X
- XI
- XII

Hanging objects may swing.

The whole interior of a building vibrates.

Glass windows break.

The shaking is perceptible to everybody.

Everyone is aware of the earthquake. People flee outside.

Buildings are damaged. Cracks form in the ground.

Railroad tracks are twisted.

Total destruction. Waves are visible on the ground.

The shaking is felt by people inside.

Walls crack.

Trees shake.

Walls pop out of their frames.

Widespread panic.

Fires break out.

Windows and doors vibrate.

People flee outside.

No structure is left standing.

The ground splits open and sinks.

Parked cars rock back and forth.

Church bells sound.

Drivers lose control of vehicles.

Partial collapse.

Mounds of sand and mud well up.

Wide cracks form in the ground.

Water service is disrupted.

Tremors registered only by seismographs.

Animals become upset and anxious.

- 2
- 2.5
- 3.5
- 4.0
- 5.5
- 6.0
- 6.5
- 7.0
- 7.5
- 8.0
- 8.5
- 9.0

Registered only by seismographs.

Very few people feel the tremor.

The tremor is felt. Only minor damages.

Most people perceive the quake.

Some buildings are lightly damaged.

May cause severe damage.

Unstable buildings are destroyed.

May cause heavy damage in populated areas.

Major earthquake. Causes extensive damage.

Considered a great earthquake.

Causes very extensive damage.




Very great earthquake. Total destruction.

Violent Seas

A large earthquake or volcanic eruption can cause a tsunami, which means "wave in the harbor" in Japanese. Tsunamis travel very fast, up to 500 miles per hour (800 km/h). On reaching shallow water, they decrease in speed but increase in height. A tsunami can become a wall of water more than 33 feet (10 m) high on approaching the shore. The height depends partly on the shape of the beach and the depth of coastal waters. If the wave reaches dry land, it can inundate vast areas and cause considerable damage. A 1960 earthquake off the coast of Chile caused a tsunami that swept away communities along 500 miles (800 km) of the coast of South America. Twenty-two hours later the waves reached the coast of Japan, where they damaged coastal towns. ●


How It Happens

A tremor that generates vibrations on the ocean water's surface can be caused by seismic movement on the seafloor. Most of the time the tremor is caused by the upward or downward movement of a block of oceanic crust that moves a mass of ocean water. A volcanic eruption, meteorite impact, or nuclear explosion can also cause a tsunami.



7.5
Only earthquakes above this magnitude on the Richter scale can produce a tsunami strong enough to cause damage.

津波
The word tsunami comes from Japanese
TSU NAMI
Harbor Wave



After a catastrophe

The illustration shows a satellite image of Khao Lak, in the coastal province of Phang Nga in southwestern Thailand. The picture was taken three days after the great tsunami of Dec. 26, 2004, that was caused by the colliding Eurasian and Australian plates near Indonesia. This was the greatest undersea earthquake in 40 years. Below, the area as it looked two years earlier. ●

Dec. 29, 2004

The hypothetical line shows how far inland the tsunami reached. Over half a mile (0.8 km) of the coast was swept away by the tidal wave. Eighty percent of the surface in Khao Lak's tourist area was destroyed.

1,000

Deaths caused by the tsunami in this area alone.

Thailand had the greatest number of tourist deaths.

Everything swept away by the wave was left piled up on the beach. Coastline before the tsunami. The coastline was devastated.

The tropical forests along the beach of Cape Pankarang were wiped out.

Bamboo Orchid Resort

CAPE PANKARANG

Palm Galleria Resort

Pankarang Beach Cottage

South Sea Pankarang

Blue Village Pankarang Resort

River levels rose after the catastrophe.

The river's mouth was completely flooded.

Area flooded by the wave

3,300-4,900 feet (1,000-1,500 m)

Many beaches lost all their sand.

Sofitel Magic Lagoon Resort

Grand Diamond Resort and Spa

Theptaro Lagoon Resort

Geological section

feet (m)
1,650 (500)




THAILAND

Latitude 16° N
Longitude 100° E

Surface area	198,114 square miles (513,115 sq km)
Population	63,100,000
Population density	289 people per square mile (112.9 people/sq km)
Tsunami-related deaths	5,248
Persons missing in tsunami	4,499

ANDAMAN SEA



Jan. 13, 2003

Nearly two years before the tragedy, wide areas of lush vegetation, fine, white sand beaches, and many buildings enhanced the natural attractions of this tourism center.

10:00 a.m.

Time when the wave hit the beach.



INDIAN OCEAN

Surface area	28.3 million square miles (73.4 million sq km)
Percentage of Earth's surface	14%
Percentage of total volume of the oceans	20%
Length of plate boundaries (in focus)	745 miles (1,200 km)
Countries affected in 2004	21

Cause and Effect

On Dec. 26, 2004, an earthquake occurred that measured 9.0 on the Richter scale, the fifth greatest on record. The epicenter was 100 miles (160 km) off the west coast of Sumatra, Indonesia. This quake generated a tsunami that pummeled all the coasts of the Indian Ocean. The islands of Sumatra and Sri Lanka suffered the worst effects. India, Thailand, and the Maldives also suffered damage, and there were victims as far away as Kenya, Tanzania, and Somalia, in Africa.

7:58
Local time when the tsunami was unleashed (00:58 universal time)

THE VICTIMS
On this map, the number of confirmed deaths and the number of missing persons in each country are added together, giving an estimated total death toll. In addition, 1,600,000 persons had to be evacuated.



Duration

The tremor lasted between 8 and 10 minutes, one of the longest on record. The waves took six hours to reach Africa, over 5,000 miles (8,000 km) away.

ARABIAN PLATE

SOMALIA
Pop. 8,863,338
289 dead

KENYA
Pop. 34,707,817
1 dead

TANZANIA
Pop. 37,445,392
13 dead

INDIAN PLATE

MALDIVES
Pop. 339,330
108 dead

INDIA
Pop. 1.065 billion
18,045 dead

Vishakhapatnam
Bangalore
Cochin
Madras
Pulmoddal
Batticaloa
Colombo
Matara

SRI LANKA
Pop. 19,905,165
35,322 dead

AFRICAN PLATE

500 miles per hour (800 km/h)
Speed of the first wave

BANGLADESH
Pop. 141,340,476
2 dead

Dhaka
Calcutta

MYANMAR
Pop. 42,720,196
600 dead

Mandalay
Rangoon (Yangon)

EURASIAN PLATE

ASIA

THAILAND
Pop. 64,865,523
8,212 estimated dead

MALAYSIA
Pop. 23,522,482
74 dead

PHILIPPINE PLATE

PACIFIC PLATE


INDONESIA
Pop. 238,452,952
167,736 dead

4 inches per year (1.0 cm/year)


1h

EPICENTER
3° 18' N
95° 47' E


Magnitude 9
Multiple aftershocks of up to magnitude 7.3.



2 The wave begins
Large waves are detected northwest and southeast of the epicenter.



3 First impact
A 33-foot-high (10 m) wave destroys Banda Aceh, Indonesia, reaching 2.5 miles (4 km) inland.



The tsunami's advance.

A seismic station in Australia detected the seismic movement that later caused the great tsunami that struck the nearest coastlines with waves more than 33 feet (10 m) high. An hour and a half later, the tsunami reached Sri Lanka and Thailand. The tsunami had seven crests, which reached the coasts at 20-minute intervals. By the time the tsunami arrived at the coast of Africa hours later, the waves had been greatly diminished.

LEGEND

- Most-affected areas
- Plate movements at different speeds
- Time it took the wave to reach the indicated dotted line.
- Movement of the wave.

Study and Prevention

NORTHRIDGE
The 1994 earthquake in this California city measured 6.7 on the Richter scale and caused approximately 60 deaths and damage estimated at a value of \$40,000,000,000.

- RISK AREAS** 76-77
- PRECISION INSTRUMENTS** 78-79
- CONTINUOUS MONITORING** 80-81
- STABLE BUILDINGS** 82-83
- ON GUARD** 84-85
- SAN FRANCISCO IN FLAMES** 86-89
- HISTORIC EARTHQUAKES** 90-91



Predicting earthquakes is very difficult because of a large number of variables, because no two fault systems are alike. That is why populations that have

settled in areas with high seismic risk have developed a number of strategies to help everyone know how to act should the earth begin to shake. California and Japan are examples of densely populated

regions whose buildings, now designed according to a stable construction model, have saved many lives. There children are trained periodically at their schools: they do practice drills, and they know where to

look for cover. Experts have learned many things about earthquakes in their attempt to understand the causes of these tremors, but they still are not able to predict when an earthquake will take place. ●

Risk Areas

A seismic area is found wherever there is an active fault, and these faults are very numerous throughout the world. These fractures are especially common near mountain ranges and mid-ocean ridges. Unfortunately, many population centers were built up in regions near these dangerous places, and, when an earthquake occurs, they become disaster areas. Where the tectonic plates collide, the risk is even greater. ●



Most-vulnerable regions


They are unpredictable, and among the most destructive of natural phenomena. Earthquakes shake the earth. They open and move it, and, within a few seconds, they can turn a peaceful city into the worst disaster area, an area in which seismic activity and a high population density coincide. But in the open country, where earthquakes have much less effect, we can conclude that it is not earthquakes, but buildings, that kill people.

Precision Instruments

The destructive potential of earthquakes gave rise to the need to study, measure, and record them. Earthquake records, called "seismograms," are produced by instruments called "seismographs," which basically capture the oscillations of a mass and transform them into signals that can be measured and recorded. An earthquake is usually analyzed by means of three seismographs, each oriented in a unique direction at a given location. In this way one seismograph detects the vibrations produced from north to south, another records those from east to west, and a third detects vertical vibrations, those that go up and down. With these three instruments, a seismic event can be reconstructed. ●

Seismometers in History

Modern seismometers have digital mechanisms that provide maximum precision. The sensors are still based on seismic energy moving a mechanical part, however, and that is essentially the same principle that operated the first instrument used to evaluate earthquakes. It was invented by a Chinese mathematician almost 2,000 years ago. Beginning with his invention, the mechanism has been perfected to what it is today.



123

HENG'S SEISMOSCOPE

The first known seismometer was Chinese. The metallic pendulum mass hung from the cover of a large bronze jar. The small balls fell from the mouths of the dragons to the mouths of the frogs, depending on the direction of the seismic movement. Some of these models were 6 feet (2 m) tall.

ZHANG HENG
Chinese mathematician, astronomer, and geographer (AD 78-139), also invented the odometer, calculated the number pi as the square root of 10 (3.16), and corrected the calendar.

1950

PORTABLE SEISMOMETER

Their strong structure allowed these seismometers to be installed in the field. This model translated movement to electric impulses so the signal could be transmitted over some distance.

1906

BOSCH-OMORI SEISMOMETER

Is a horizontal pendulum with a pen that makes a mark directly on a paper roll. With it, Omori, a Japanese scientist, registered the 1906 earthquake in San Francisco.


1980

WILMORE PORTABLE SEISMOMETER

A sensitive mass vibrates and moves to the rhythm of the seismic energy inside this tube-shaped mechanism. An electromagnet translates this vibration to electric signals, which are transmitted to a computer that records the data.

Pioneers of seismology

The defining principle of modern seismology emerged from relating earthquakes to the movement of the continents, but that did not take place until well into the 20th century. Starting in the 19th century, however, many scholars contributed elements that would be indispensable.




ROBERT MALLET
From Dublin, Ireland (1810-81). Carried out important studies on the speed of the propagation of earthquakes, even before having experienced one.



JOHN MILNE
British geologist and engineer (1850-1913), created a needle seismograph, a forerunner of current seismographs, and related earthquakes to volcanism.



RICHARD OLDHAM
British (1858-1936). Published a study in 1906 on the transmission of seismic waves, in which he also proposed the existence of the Earth's core.



Continuous Movement

Humankind has tried throughout history to find a way to predict earthquakes. Today, this is done through the installation of seismic observatories and of various field instruments that gather information and compare it to the data sent by scientists from other locations. Based on these records, it is possible to evaluate the chances that a great earthquake is developing and act accordingly. ●

Observing from a Distance

Seismologists place instruments at fault lines in earthquake-prone areas. Later, at the seismologic observatory, the information taken by field instruments is compiled, and any significant change is noted. If anything suggests that an earthquake is about to take place, emergency services are alerted. Most of these instruments are automatic, and they send digital data through the telephone system.

Seismologic Networks

Installing complex detection systems would not be of much use if the systems worked in an isolated manner and were not able to share the information they generated. There are national and international seismologic networks that, by means of communications technology, send their observations to other areas that might be affected.

NETWORK OF NETWORKS


Findings in an area can have repercussions at a great distance. The immediate availability of data allows for linked work.

SATELLITES

Some are used by the GPS systems, but others are critical because they take photographs with extreme accuracy, and they are thus able to record indicators that can be communicated quickly to the base.

LABORATORY

Networking at the research centers allows for the comparison of data and provides a global vision that broadens the predictive power of science.



Stable Buildings

In cities located in seismic areas, buildings must be designed and constructed with an earthquake-resistant structure that can adequately withstand the movements caused by an earthquake. Foundations are built with damping so that they can absorb the force of the seismic movement. Other buildings have a large metallic axis, around which the stories of the building can oscillate without falling. Currently the amount of knowledge on the effect of earthquakes on structures, as well as knowledge on the behavior of different materials, allows for the construction of less-vulnerable buildings. ●




ROPONGI HILLS
TOKYO, JAPAN
Latitude 36° N
Longitude 140° E

Covered area	4,089,930 square feet (380,105 sq m)
Stories	54 (+6 underground)
Width	275 feet (84 m)
Height	780 feet (238 m)


Why Pagodas in Japan Do Not Fall

Japanese pagodas have survived centuries of earthquakes. They are five stories tall, and higher sections of the building are smaller than lower parts. The pagodas are held up by a central pillar that acts as the only support for the building. During a quake, each floor balances independently, without transmitting the oscillating force to the other floors.



Swaying Principle
Each floor also has a symmetric structure. During an earthquake, the ends opposite the eaves act as a counterbalance to achieve equilibrium.

ROPONGI HILLS TOWER
Located in Tokyo, its structure consists of simple geometric bodies, symmetrically placed, without any irregularities in shape. The tower is formed by a massive central framework and a lightweight and flexible exterior framework.



898 FEET
(274 m)
56 STORIES

Earthquake-Resistant Architecture

There are many ways to design an earthquake-resistant structure: the distribution of walls, the joints between beams and columns, and geometric simplicity. There are also earthquake simulators, large platforms that shake a structure to test it. The

simulators are used to test materials and study the forces that act on them. A building's true earthquake resistance, though, can be proven only when it has been built and has survived actual earthquakes.

STRUCTURE

To avoid imbalances, the upper elements of a structure must be located over only a few axes, without any isolated vertical segments.






AVOIDANCE OF OFF-CENTER JOINTS

If the beam remains still when the wall moves, the joint breaks. Forces spread out over an axis with flexible material.



Suspension System

So that a building will suffer only small oscillations during an earthquake, it is isolated and built in a large trench, separated by special devices. In addition, because the higher floors move more than the lower ones, mechanical dampers are employed diagonally so as to be more highly tensioned on top than on the bottom. This makes the structure as a whole more flexible, but it also offers resistance to sudden variations.



BASE ISOLATION

A system made of steel disks, interspersed with plates made of a soft material, softens the transmission of seismic movements from the ground to the building.

Plates 0.12 inch (3 mm) thick alternate with elastic rubber layers.

Lead core

THE INTELLIGENT BUILDING
When an earthquake is detected, a computer-controlled system provides variable compression to the dampers, which absorb the movements according to the height of the floor and the intensity of the vibrations.

DAMPERS
Are made of pistons filled with oil. They reduce the force of horizontal movement.

STEEL TUBE

CEMENT

COLUMNS
An example of a building that shows simplicity in its geometric design and, therefore, in its behavior.

6 STORIES
UNDER
THE
GROUND

On Guard


When the earth shakes, nothing can stop it. Disaster seems inevitable, but, though it is inevitable, much can be done to diminish the extent of the catastrophe. Residents of earthquake-prone areas have incorporated a series of preventive measures to avoid being surprised and to help them act appropriately at home, at the office, or outdoors. These are basic rules of behavior that will help you survive. ●

Prevention

IF YOU LIVE IN AN EARTHQUAKE-PRONE AREA, familiarize yourself with the emergency plans for the community where you live, plan how your family will behave in the event of an earthquake, know first aid, and know how to extinguish fires.



FIRST-AID KIT
Keep a first-aid kit, and keep your vaccinations up to date.



LIGHTS
Have emergency lighting, flashlights, a transistor radio, and batteries on hand.



SECURING OBJECTS
Secure heavy objects such as furniture, shelves, and gas appliances to the wall or to the floor.



BREAKERS
Have a breaker installed, and know how to shut off the electricity and the gas supply.



FOOD AND WATER
Store drinking water and nonperishable food.




FIRST AID
Learn first aid, and participate in community earthquake-response training.

During an earthquake

AS SOON AS YOU FEEL THE EARTH UNDER YOUR FEET BEGIN TO MOVE, look for a safe place, such as beneath a doorframe or under a table, to take cover. If you happen to be on a street, head to an open space such as a square or park. It is important to remain calm and to not be influenced by people who panic.

AT HOME

It is essential that the home be built following regulations for earthquake-resistant construction and that someone be in charge of shutting off the electricity and gas supplies.



AT THE OFFICE

Offices are usually located in areas conducive to bringing large groups of people together. Thus it is recommended that you remain where you are and not rush to the exits. When people panic, there is a greater probability of their being crushed by a crowd than by a building, especially in buildings that contain a lot of people.

Mark escape routes and keep them free of obstacles.

Know where emergency equipment, such as fire extinguishers, hoses, and axes, is located.

Seek protection under a table or desk to avoid being hurt by falling objects.

Stay away from windows and balconies.

Do not use elevators; the electricity might be cut off.

Objects that could fall because of movement should be attached to the wall.

In case of evacuation, stairs are the safest place, but they could become filled with people.

It is good to designate a leader who can guide others. Form a human chain to prevent getting lost and to prevent accidents.

Toxic or flammable materials must not be in danger of spilling.

Do not light matches or flames; use flashlights.

Do not drink tap water because it might be polluted.

Fires are frequently more dangerous than the earthquake itself. They can easily get out of control and spread through the city.

Do not run on the street; doing so will cause panic.

If you are in a vehicle, stop in the safest place possible (away from large buildings, bridges, and utility poles). Do not leave your car unless it becomes necessary to do so.


IN PUBLIC PLACES

When you are outside, it is important to keep away from tall buildings, light poles, and other objects that could fall. The safest course of action is to head to a park or other open space. If the earthquake takes you by surprise while you are driving, stop and remain in the car, but make sure you are not close to any bridges.

Head toward open spaces such as squares and parks, and move away from any trees to the extent possible.

Coastlines

Do not approach the coastline because of the possibility of a tsunami. Also avoid rivers, which could develop strong currents.



Follow the instructions of civil defense officers.

Fixing breaks in water and gas lines is a priority.

Stay away from buildings, walls, utility poles, and other objects that could fall.

Rescue Tasks

ONCE THE EARTHQUAKE ENDS, rescue tasks must begin. At this stage it is imperative to determine whether anyone is injured and to apply first aid. Do not move injured people who have fractures, and do not drink water from open containers.

RESCUERS

The first priority after an earthquake is to search for survivors.

DOGS

Specially trained animals with protective helmets and masks can search for people under the rubble.

TRANSPORTATION

It is important to keep access routes to affected areas open to ensure entry by emergency teams.



San Francisco in Flames

The earthquake that shook San Francisco on April 18, 1906, was a major event: in only a few seconds, a large part of one of the most vital cities of the United States was reduced to rubble. Suddenly, centuries of pent-up energy was released when the earthquake, measuring 8.3 on the Richter scale, devastated the city. Though the earthquake destroyed many buildings, the worst damage was caused by the fires that destroyed the city in the course of three days, forcing people to flee their homes. ●

April 18

1 EVERYTHING STARTED LIKE THIS.

On April 18, 1906, at 5:12 a.m., the Pacific Plate experienced movement of approximately 19 feet (6 m) along its 267-mile (430-km) length along the northern San Andreas fault. The earthquake's epicenter lay 39 miles (64 km) north of

San Francisco. In seconds, the earth began to move, and the majority of the city's buildings collapsed. The trolleys and carriages that were moving through the cobblestoned streets of the city were reduced to rubble.

CITY HALL

The facade was crowned by a dome that was supported by a system of columns on a steel structure. It was considered one of the city's most beautiful buildings.

History of City Hall

Until the earthquake struck, City Hall had been the seat of city government and the symbol of the city. Built in the second half of the 19th century, it represented a time of accelerated growth, powered by the gold riches of the state of California. Construction began on Feb. 22, 1870, and ended 27 years later, after many revisions to architect Auguste Laver's original project. While it stood, City Hall was said to have been constructed with bricks held together with corruption, typical of a time of easy money and weak institutions. The total cost of the work rose to a little more than \$6,000,000 of that time, and, according to current calculations, it is estimated that it was prepared to withstand an earthquake up to a magnitude of 6.6. Only the dome and the metal structure were left standing. The remnants of the building were demolished in 1909.

THE FACE OF THE BUILDING COLLAPSED.
The facade collapsed completely on top of the rotunda at its base.



**UNITED STATES
SAN FRANCISCO,
CALIFORNIA**
Latitude 42° 40' N
Longitude 122° 18' W

Surface area	46 square miles (120 sq km)
Population	739,426
Population density	16,000 people per square mile (6,200 people/sq km)
Perceptible earthquakes felt annually	100 - 150
Total earthquakes per year	~ 10,000

April 20

3 THE GREAT FIRE
Two days later, what had begun as a localized fire had become an inferno that consumed the city. There were mass evacuations of people to distant areas, while the army dynamited some buildings. Firefighters had to control the flames using seawater.

3 years

4 REBUILDING
The city reemerged from the ashes, powered by its wealth and economic importance. Losses are estimated to have reached \$5,000,000,000 in present-day dollars, and, until Hurricane Katrina struck in 2005, the 1906 earthquake was the greatest natural disaster the United States had experienced.

5:12 a.m.

2 THE EARTHQUAKE
Not only was the earthquake extremely violent, but it oscillated in every direction for 40 seconds. People left their houses and ran down the streets, completely stunned and blinded by fear. Many buildings split

open, and others became piles of rubble. A post office employee related that "The walls were thrown into the middle of the rooms, destroying the furniture and covering everything with dust."

GAS LIGHTING
Gas lighting was one of the signs of progress that gave prominence to the city.

Clearing the Rubble

It is calculated that some 3,000 people died in the 1906 catastrophe, trapped in their destroyed homes or burned by the fire the earthquake started. In the following weeks, the army, firefighters, and other workers deposited the

rubble in the bay, forming new land, which is today known as the Marina District. Little by little, traffic resumed in the major streets, and the trolley system was reestablished. Six weeks after the earthquake, banks and stores opened for business.




Workers pose while they demolish a house.

WORKERS

By Saturday, April 21, some 300 plumbers had entered the city to reestablish services, mainly the water system. During the following weeks, thousands of workers tore down unstable buildings, prepared the streets for traffic, and cleared the city of rubble. Nearly 15,000 horses were used to haul rubble.

SHORTLY AFTERWARD

This panoramic photograph shows the destruction of the city. Despite the destruction, many buildings were left standing.



SAINT MARY'S CHURCH

CHINATOWN

Was completely destroyed by the fire.



18,000

BUILDINGS OF THAT PERIOD


are still standing, despite the 1906 earthquake and the tremors that passed through the city afterward.

Three Days of Fire

The great fire that followed the earthquake expanded quickly. Firefighters, in a desperate attempt to block the spread of the fire, used explosives to make firebreaks because there was no water supply available. The army evacuated the area, and people could not take anything with them. During the three days when the city burned, it is speculated that many homeowners burned their houses that had been partially destroyed by the earthquake, in order to be able to collect insurance money. Other things that contributed to the fire were the intentional explosions that, at first badly implemented, spread the fire. By the fourth day, the center of the city was reduced to ashes.

REFUGEE CAMPS

The army set up field camps in the parks to house those who had lost everything. Months later, the government built temporary homes for about 20,000 people.




FIELD LUNCH

The army set up kitchens in the camps. There was always food in these field kitchens, and there was even a free ration of tobacco for every person.

Army tents to house refugees.

- 1 The fire began in the Market Street area, south of the city in the worker's district, where many houses were made of wood.
- 2 On the second day, the fire spread west. About 300,000 people were evacuated from the bay in ferries.



- 3 During the third day, the fire swept through Chinatown and North Beach, causing heavy damage to the Victorian homes on North Beach hill.
- 4 Once the fire was extinguished, Russian Hill and Telegraph Hill (shown as white spots) were still intact, as was the port.

The firefighters tried to extinguish the fire.



28,000

BUILDINGS DEMOLISHED

The damage calculated to have been caused by the great earthquake. Many of these buildings, such as City Hall, were famous for their lavish architecture.

MERCHANT EXCHANGE

Built in 1903, it remained standing and was later refurbished.



MILLS BUILDING

This building in the financial district had been built in 1890.

Historic Earthquakes

The Earth is alive. It moves, it shifts, it crashes and quakes, and it has done so since its origin. Earthquakes vary from a soft vibration to violent and terrorizing movements. Many earthquakes have gone down in history as the worst natural catastrophes ever survived by humanity. Lisbon, Portugal, 1755; Valdivia, Chile, 1960; and Kashmir, Pakistan, 2005, are only three examples of the physical, material, and emotional devastation in which an earthquake can leave a population. ●



1995 KOBE, JAPAN

Magnitude	6.8 (Richter)
Fatalities	6,433
Material losses	\$100 billion

AN INFERNO
The great earthquake of Hanshin that occurred on Jan. 17, 1995, in Kobe, a Japanese port, left behind more than 6,000 dead, 38,000 injured, and 319,000 people who had to be housed in more than 1,200 emergency shelters. The Nagata District was one of the hardest-hit areas. Almost 80 percent of the victims died because the old wooden homes crumbled in the generalized fires that followed the earthquake.

AFTER THE HORROR. The world was shaken, looking at the horrendous images of how Kobe, the city by the sea, had been painfully broken to pieces.

1755 LISBON, PORTUGAL

Magnitude	8.7 (Richter)
Fatalities	62,000
Material losses	unknown

It was the Day of the Dead, and, at 9:20 in the morning, almost the entire population of Lisbon was at church. While mass was celebrated, the earth quaked, and this earthquake would be one of the most destructive and lethal in history. The earthquake unleashed a tsunami that was felt from Norway to North America and that took the lives of those who had sought shelter in the river.

1960 VALDIVIA, CHILE

Magnitude	9.5 (Richter)
Fatalities	5,700
Material losses	\$500 million

Known as the Great Chilean Earthquake, this was the strongest earthquake of the 20th century. The surface waves produced were so strong that they were still being registered by seismometers 60 hours after the earthquake. The earthquake was felt in various parts of the planet, and a huge tsunami spread through the Pacific Ocean, killing more than 60 people in Hawaii. One of the most powerful earthquakes in memory, its aftershocks lasted for more than a week. More than 5,000 people died, and nearly two million people suffered damage and loss.

1906 SAN FRANCISCO, U.S.

Magnitude	8.3 (Richter)
Fatalities	3,000
Material losses	\$5 billion

The city was swept by the earthquake and by the fires that followed it. The quake was the result of the rupture of more than 40 miles of the San Andreas fault. It is the greatest earthquake in the history of the United States: 300,000 people were left homeless, and property losses reached millions in 1906 dollars. Buildings collapsed, the fires spread for three days, and the water lines were destroyed.

1985 MEXICO CITY, MEXICO

Magnitude	8.1 (Richter)
Fatalities	11,000
Material losses	\$1 billion

The city shook on September 19. Two days later, there was an aftershock measuring 7.6 on the Richter scale. In addition to 11,000 deaths, there were 30,000 injured, and 95,000 people were left homeless. As the Cocos Plate slid under the North American Plate, the North American Plate fractured, or split, 12 miles (20 km) inside the mantle. The vibrations of the ocean floor off the southwestern coast of Mexico provoked a tsunami and produced energy 1,000 times as great as that of an atomic bomb. Strong seismic waves reached as far east as Mexico City, a distance of 220 miles (350 km).

2004 SUMATRA, INDONESIA

Magnitude	9.0 (Richter)
Fatalities	230,507
Material losses	incalculable

An earthquake whose epicenter crossed the island of Sumatra, Indonesia, took place on December 26. This earthquake generated a tsunami that affected the entire Indian Ocean, primarily the islands of Sumatra and Sri Lanka, and reached the coasts of India, Thailand, the Maldives, and even Kenya and Somalia. This was a true human tragedy, and the economic damages were incalculable.

2005 KASHMIR, PAKISTAN

Magnitude	7.6 (Richter)
Fatalities	80,000
Material losses	\$595 million

Also known as the Indian Subcontinent Earthquake, the North Pakistan Earthquake, and the South Asian Earthquake. It occurred on Oct. 8, 2005, in the Kashmir region between India and Pakistan. Because schools were in session when the earthquake struck (9:20 a.m.), many of the victims were children, who died when their school buildings collapsed. It was the strongest earthquake experienced by the region for a century. Three million people lost their homes. The most-heavily affected areas lost all their cattle. Entire fields disappeared under earth and rock. The epicenter was located near Islamabad, in the mountains of Kashmir, in an area governed by Pakistan.

Glossary

Aa

Type of lava flow that presents sharp projections on its surface when it hardens.

Abrasion

Modification of rock surfaces by friction and by the impact of other particles transported by wind, water, and ice.

Active Volcano

Volcano that erupts lava and gas at regular intervals.

Aerosol

Small particles and drops of liquid scattered in the air by volcanic gases.

Aftershock

Small temblor or quake produced as rock settles into place after a major earthquake.

Aseismic

The characteristic of a building designed to withstand oscillations, or of areas with no seismic activity.

Aseismic Region

Tectonically stable region of the Earth, where there are almost no earthquakes. For example, the Arctic region is aseismic.

Ashfall

Phenomenon in which gravity causes ash (or other pyroclastic material) to fall from a smoke column after an eruption. The distribution of the ash is a function of wind direction.

Asthenosphere

Internal layer of the Earth that forms part of the mantle.

Avalanche

Rapid movement of enormous volumes of rock and other materials caused by instability on the flanks of the volcano. The instability can be caused by the intrusion of magma into the structure of the volcano, by a large earthquake, or by the weakening of the volcano's structure by hydrothermal variation, for example.

Ballistic (Fragment)

A lump of rock expelled forcefully by a volcanic eruption and that follows a ballistic or elliptical trajectory.

Baltic

Of or pertaining to the Baltic Sea, or to the territories along it.

Batholith

Massive body of magma that results from an intrusion between preexisting layers.

Caldera

Large, round depression left when a volcano collapses onto its magma chamber.

Convection Currents

Vertical and circular movement of rock material in the mantle but found exclusively in the mantle.

Convergent Boundary

Border between two colliding tectonic plates.

Core

Central part of the Earth, with an outer boundary 1,800 miles (2,900 km) below the Earth's surface. The core is believed to be composed of iron and nickel—with a liquid outer layer and a solid inner core.

Crater

Depression on the peak of a volcano, or produced by the impact of a meteorite.

Crust

Outermost, rigid part of the Earth, made up mostly of basaltic rocks (underneath the oceans) and of rocks with a higher silicate content (in the continents).

Density

Ratio of a body's mass to its volume. Liquid water has a density of 62.4 pounds per cubic foot (1 g/cu cm).

Dike

Tabular igneous intrusion that crosses through layers of surrounding rock.

Dome

Cup-shaped bulge with very steep sides, formed by the accumulation of viscous lava. Usually a dome is formed by andesitic, dacitic, or rhyolitic lava, and the dome can reach a height of many hundreds of feet.

Duration of Earthquake

Time during which the shaking or tremor of an earthquake is perceptible to humans. This period is always less than that registered by a seismograph.

Earthquake

Vibration of the Earth caused by the release of energy.

Eon

The largest unit of time on the geologic scale, of an order of magnitude greater than an era.

Epicenter

Point on the Earth's surface located directly above the focus of an earthquake.

Epicentral Area

Region around the epicenter of an earthquake, usually characterized by being the area where the shaking is most intense and the earthquake damage is greatest.

Epicentral Distance

Distance along the Earth's surface from the point where an earthquake is observed to the epicenter.

Extinct Volcano

Volcano that shows no signs of activity for a long period of time, considered to have a very low probability of erupting.

Fault Displacement

Slow, gradual movement produced along a fault. It is characterized by not generating an earthquake or tremor.

Focus

Internal zone of the Earth, where seismic waves are released, carrying the energy held by rocks under pressure.

Fumarole

Emission of steam and gas, usually at high temperatures, from fractures or cracks in the surface of a volcano or from a region with volcanic activity. Most of the gas emitted is steam, but fumarole emissions can include gases such as CO₂, CO, SO₂, H₂S, CH₄, HCl, among others.

Geothermal Energy

Naturally heated steam used to generate energy.

Geyser

Spring that periodically expels hot water from the ground.

Gondwana

Southern portion of Pangea, which at one time included South America, Africa, Australia, India, and Antarctica.

Hot Spot

Point of concentrated heat in the mantle capable of producing magma that shoots up to the Earth's surface.

Hydrothermal Alteration

Chemical change in rocks and minerals, produced by an aqueous solution that is rich in volatile chemical elements found at high temperature and that rises from a magma body.

Igneous Activity

Geologic activity involving magma and volcanic activity.

Incandescent

A property of metal that has turned red or white because of heat.

Lahar

Mudflows produced on the slopes of volcanoes when unstable layers of ash and debris become saturated with water and flow downhill.

Lapilli

Fragments of rock with a diameter between 0.06 and 1.3 inches (2 and 32 mm) expelled during a volcanic eruption.

Lava

Magma, or molten rock, that reaches the Earth's surface.

Lava Bombs

Masses of lava that a volcano expels, which have a diameter equal to or greater than 1.2 inches (3.2 cm).

Lava Flow

River of lava that flows out of a volcano and runs along the ground.

Liquefaction

Transformation of ground from solid to fluid state through the action of an earthquake.

Lithosphere

Rigid part of the outer layer of the Earth, formed by the crust and the outer layer of the mantle. This is the layer that is destroyed in subduction zones and that grows in mid-ocean ridges.

Magma

Mass of molten rock deep below the surface, which includes dissolved gas and crystals. When magma has lost its gases and reaches the surface, it is called lava. If magma cools within the Earth's crust, it forms plutonic rocks.

Magma Chamber

Section within a volcano where incandescent magma is found.

Mantle

Layer between the Earth's crust and the outer core. Its lower part, the asthenosphere, is partially molten. The more superficial and less-fluid outer part is called the lithosphere.

Mid-Ocean Ridge

An elongated mountain range on the ocean floor, which varies between 300 and 3,000 miles (500 and 5,000 km) in breadth.

Neck

Column of lava that has solidified inside a volcano.

Normal Fault

Fracture in rock layers where the ground is being stretched, which generally causes the upper edge to sink relative to the lower part.

Ocean Trench

Long, narrow, extremely deep area of the ocean floor formed where the edge of an oceanic tectonic plate sinks beneath another plate.

Pahoehoe Lava

Lava with a smooth surface that has a ropelike form.

Pelean Eruption

Type of volcanic eruption with a growing dome of viscous lava that may be destroyed when it collapses because of gravity or brief explosions. Pelean eruptions produce pyroclastic flows or burning clouds. The term comes from Mount Pelée in Martinique.

Permeable Layers

Strata of the Earth's crust that allow water to reach deeper layers.

Plate Tectonics

Theory that the Earth's outer layer consists of separate plates that interact in various ways, causing earthquakes and forming volcanoes, mountains, and the crust itself.

Plinian Eruption

Extremely violent and explosive type of volcanic eruption that continuously expels large quantities of ash and other pyroclastic materials into the atmosphere, forming an eruption column typically 5 to 25 miles (8 to 40 km) high. The term honors Pliny the Younger, who observed the eruption of Mount Vesuvius (Italy) in AD 79.

Plume

Column of hot rock that rises from within the mantle, inside of which the rock may melt.

Primary (P) Wave

Seismic wave that alternately compresses and stretches the ground along its direction of travel.

Pumice

Pale volcanic rock full of holes, which give it a low density. Its composition is usually acidic (rhyolitic). The holes are formed by volcanic gases that expand as volcanic material rises to the surface.

Pyroclastic Flow

Dense, hot mix of volcanic gas, ash, and rock fragments that flows rapidly down the sides of a volcano.

Reverse Fault

Fractures in rock layers where the ground is being compressed, which generally causes the upper edge to rise above the lower part in a plane inclined between 45 and 90 degrees from the horizontal.

Richter Scale

Measures the magnitude of an earthquake or of the energy it releases. The scale is logarithmic, such that an earthquake of magnitude 8 releases 10 times as much energy as a magnitude 7 quake. An earthquake's magnitude is estimated based on measurements taken by seismic instruments.

Rift Zone

Area where the crust is splitting and stretching, as shown by cracks in the rock. Such areas are produced by the separation of tectonic plates, and their presence causes earthquakes and recurrent volcanic activity.

Scale of Intensity

Scale used to measure the severity of movement of the ground produced by an earthquake. Degrees of intensity are assigned subjectively depending on how the tremor is perceived and according to the damage caused to buildings. A widely used scale is the Mercalli scale.

Secondary (S) Wave

Transverse or cross-section wave with motion perpendicular to the direction of its travel.

Seismic Event

Shaking of the ground caused by an abrupt and violent movement of a mass of rock along a fault, or fracture, in the crust. Active volcanoes cause a wide variety of seismic events.

Seismic Gap

Fault zone, or zone of a segment at the boundary between tectonic plates, with a known seismic history and activity, which records a period of prolonged calm, or of seismic inactivity, during which large amounts of elastic energy of deformation accumulate, and that, therefore, presents a greater probability of rupture and occurrence of a seismic event.

Seismic Hazard Calculation

Process of determining the seismic risk of various sites in order to define areas with similar levels of risk.

Seismic Risk

The probability that the economic and social effects of a seismic event will exceed certain preestablished values during a given period, for example, a certain number of victims, an amount of building damage, economic losses, etc. Also defined as the comparative seismic hazard of one site relative to another.

Seismic Wave

Wavelike movement that travels through the Earth as a result of an earthquake or an explosion.

Seismic Zone

Limited geographic area within a seismic region, with similar seismic hazard, seismic risk, and earthquake-resistant design standards.

Seismograph

Instrument that registers seismic waves or tremors in the Earth's surface during an earthquake.

Seismology

Branch of geology that studies tremors in the Earth, be they natural or artificial.

Shield Volcano

Large volcano with gently sloping flanks formed by fluid basaltic lava.

Silicon

One of the most common materials, and a component of many minerals.

Subduction

Process by which the oceanic lithosphere sinks into the mantle along a convergence boundary. The Nazca Plate is undergoing subduction beneath the South American Plate.

Subduction Zone

Long, narrow region where one plate of the crust is slipping beneath another.

Surface Wave

Seismic wave that travels along the Earth's surface. It is perceived after the primary and secondary waves.

Swarm of Earthquakes

Sequence of small earthquakes that occur in the same area within a short time period, with a low magnitude in comparison to other earthquakes.

Symmetry

Correspondence that exists in an object with respect to a center, an axis, or a plane that divides it into parts of equal proportions.

Tectonic Plates

Large, rigid sections of the Earth's outer layer. These plates sit on top of a more ductile and plastic layer of the mantle, the asthenosphere, and they drift slowly at an average rate of 1 inch (2.4 cm) or more per year.

Thrust Fault

A fracture in rock layers that is characterized by one boundary that slips above another at an angle of less than 45 degrees.

Transform Fault

Fault in which plate boundaries cause friction by sliding past each other in opposite directions.

Tremor

Seismic event perceived on the Earth's surface as a vibration or shaking of the ground, without causing damage or destruction.

Tsunami

Word of Japanese origin that denotes a large ocean wave caused by an earthquake.

Viscous

Measure of a material's resistance to flow in response to a force acting on it. The higher the silicon content, the higher the viscosity.

Volcanic Glass

Natural glass formed when molten lava cools rapidly without crystallizing. A solid-like substance made of atoms with no regular structure.

Volcanic Ring

Chain of mountains or islands located near the edges of the tectonic plates and that is formed as a result of magma activity associated with subduction zones.

Volcano

Mountain formed by lava, pyroclastic materials, or both.

Volcanology (Vulcanology)

Branch of geology that studies the form and activity of volcanoes.

Vulcanian Eruption

Type of volcanic eruption characterized by the occurrence of explosive events of brief duration that expel material into the atmosphere to heights of about 49,000 feet (15 km). This type of activity is usually linked to the interaction of groundwater and magma (phreatomagmatic eruption).

Water Spring

Natural source of water that flows out of the crust. The water comes from rainwater that seeps into the ground in one place and comes to the surface in another, usually at a lower elevation. Because the water is not confined in waterproof chambers, it can be heated by contact with igneous rock. This causes it to rise to the surface as hot springs.

Index

A

aa lava flow, 30
abyssal plain, 16
Africa, 15, 16, 72
African plate, 77
Antarctic plate, 76, 77
Antarctica, 15
Antilles, volcanoes, 47
Arabian plate, 77
Archean Eon, 11
architecture, 82, 83
Argentina
 Incahuasi, 46
 Llullaillaco, 46
 Ojos del Salado, 46
 Tipas, 46
Armenia, earthquake of 1988, 77
ash, 8, 26, 28
 composition, 30
 effects, 35, 50
 protection, 51
Asia, 15, 19
asthenosphere (layer of the Earth), 13, 17
Atlantic Ocean, 16–17
atmosphere, 13, 35
atoll, 16
 corals, 40
 formation, 40–41
 volcanic islands, 41
Australian plate, 76
Avachinsky volcano, 46
avalanche, 32–33, 57

B

Bangladesh, 73
batholith, 12
Bolivia, Sajama, 46

C

caldera, 26, 29
Caldera Blanca volcano, 29
California, 23
Caribbean plate, 76, 77
Chapel of St. Michael (France), 29
Chile
 earthquake of 1960, 77, 91
 Incahuasi, 46
 Llullaillaco, 46
 Ojos del Salado volcano, 46, 47
climate, volcanic, 56
cnidarian, 40
Cocos plate, 76, 77
Colombia, Nevado del Ruiz volcano, 36
continent, 14–15, 31
continental drift, 12, 14
continental shelf, 12, 16
coral
 branching, 40
 compact, 40
 hard coral polyp, 40
 optimal conditions, 41
 reef: See coral reef
coral reef
 atolls, 16, 40–41
 crest, 40
 face, 40
creep meter, 81

D

dike, 17, 27

E

Earth
 atmosphere, 13, 35
 core, 13, 79

crust: See Earth's crust

history, 10–11
layers, 12–13
magnetic field, 17
mantle, 13
earthquake, 18
 aftershock, 60
 Alpine fault, 60–61
 annual rate, 60
 architecture, 82–83
 classification, 63
 damage, 66–67
 detection, 66–67, 78–79, 80–81
 direct effects, 65
 EMS 98 scale, 67
 epicenter, 60
 factors that determine effects, 65
 fault plane, 60
 faults, 22, 76
 fire danger, 84
 folds, 60
 foreshock, 60
 historic, 90–91
 hypocenter, 60
 indirect effects, 65
 intensity, 66
 liquefaction, 65
 magnitude, 66
 measuring, 66–67
 modified Mercalli scale, 66
 origin, 61
 origin of word, 60
 oscillatory, 63
 pagodas, 82
 prediction, 81
 rescue, 85
 Richter scale, 66–67
 risk areas, 76–77
 safety, 84–85
 San Andreas fault, 23
 seismic energy, 62–63, 64–65
 seismic waves: See seismic waves
 seismograph, 49, 64, 66, 78–79
 specific earthquakes
 Alaska, 76

Armenia, 77
Assam, India (1897), 76
Cachemira, Pakistan, 77, 91
Chile, 77, 91
Indonesia, 91
Iran, 77
Japan, 76, 90
Loma Prieta, 59, 64
Mexico (1985), 76, 91
Portugal, 91
Roppongi Hills Tower, 82
San Francisco earthquake of 1906, 23, 86–89, 91

tectonic plates, 60, 76–77
trepidatory, 63
tsunami, 68–69, 85, 91
volcanoes, 32, 37

Earth's core, 13, 79

Earth's crust, 8, 11, 12–13
 elevations, lowest and highest, 16
 faults, 22
 layers, 13
 ocean ridges, 16, 77
 ocean trenches, 16, 77
 orogenies, 18–20
 rocks, 12

Earth's mantle, 13, 14

East Epi volcano, 46

effusive eruption, 31

El Chichón volcano, 57

Eldfell volcano, 47, 57

EMS 98 scale, 67

energy
 geothermal, 39, 42
 seismic, 62–63, 64–65
 volcanic, 33, 57

epicenter of earthquake, 60

Etna, Mount, 31, 47

Eurasia, 15

Eurasian plate, 42, 47, 77

Europe, earthquakes, 67

exosphere (layer of the atmosphere), 13

explosive eruption, 31

F

fault, 22–23
 Alpine, 60–61, 76
 displacement, 61
 earthquakes, 22, 76
 San Andreas, 23
 thrust, 18

Fiji plate, 76

Fiorelli, Giuseppe, 55

fissure eruption, 31

Fuji, Mount (Fujiyama volcano), 28, 46

fumarole, 17, 38

G

geologic time, 10–11

geyser, 38–39
 convection forces, 39
 eruptive cycle, 38–39
 geothermal fields, 38
 height, 38
 interval, 38
 locations, 38, 39, 42–43
 mineral springs, 39
 morphology of the chambers, 39

global positioning system (GPS), 48, 80, 81

Gondwana, 14, 16, 20

Grand Prismatic Spring, 38

H

Hawaiian Archipelago, 6–7, 29–30, 31, 36, 41, 44–46, 45, 56

Heng, Zhang, 78

Himalayas, 19

hypocenter (focus) of earthquake, 60, 62

I

Iceland

 Eldfell volcano, 47, 57
 Eurasian plate, 42, 47
 geothermal energy, 39, 42
 lava, 42
 North American plate, 42, 47
 Surtsey, 42
 volcanoes, 42–43

Ilamatepec, Mount (volcano), 28

India, 15, 72, 76

India plate, 77

Indian Ocean, tsunamis, 72–73

Indo-Australian plate, 76

Indonesia, 73

 earthquake of 2004, 91
 tsunami, 72–73
 volcanoes, 46

Iran, earthquake of 1990, 77

island, formation, 41, 42–43

Italy

 Etna, Mount, 31, 47
 Pompeii, 52–55
 Vesuvius, Mount, 47, 52–53, 56, 57

J

Japan, 28, 46, 76, 82, 90

K

Kenya, 72

Kilauea, Mount (volcano), 28, 31, 44, 46, 56

Kiribati, Marakei atoll, 40–41

Krafla volcano, 43

Krakatoa volcano, 34–35, 46, 57

L

lahar (mudslide), 36, 49, 51
Laki volcano, 56
Laurasia, 14
lava, 8–9

- collection, 49
- dome, 28
- eruptions, 26, 30, 31
- flows, 30, 31, 36, 44
- Iceland, 42–43
- Kalapana, 56
- measuring temperature, 48
- mid-ocean ridges, 17
- pahoehoe, 7
- rock cycle, 9

liquefaction, 65
lithosphere (layer of the Earth), 13, 16–17
Loma Prieta earthquake of 1989, 59, 64
Love wave, 63

M

magma, 8

- tectonic plates, 14–15
- volcanoes, 27

magnetic field, 17
magnetism, 17, 81
magnetometer, 81
Maka-O-Puhl volcano, 31
Malaysia, 73
Maldives, 72
Mallet, Robert, 79
Mariana Trench, 17, 76
Mauna Loa volcano, 31, 46
Mauna Ulu volcano, 29
Mercalli, Giuseppe, 67
Mercalli scale, modified, 66
mesosphere (layer of the atmosphere), 13
Mexico

- earthquakes, 76–77, 91
- volcanoes, 57

Mid-Atlantic ridge, 16–17
Milne, John, 79
mineral spring, 39
Mount...: *See under specific name, for example, Etna, Mount*
mud basin, 39
Myanmar, 73

N

Nazca plate, 77
Nevado del Ruiz volcano, 36
New Zealand

- Alpine fault, 60–61, 76
- deformation, 61
- fault, 76
- Waimangu geyser, 38

North America, 15
North American plate, 42, 77
Novarupta volcano, 46

O

ocean

- depth, 16
- growth, 16–17
- mountains, 16
- plains, 16
- ridges, 16, 77
- trenches, 16

Ojos del Salado volcano, 47
Oldham, Richard, 79
orogeny (mountain-building process), 18, 19, 20

P

Pacific plate, 23, 76
pagoda, 82
pahoehoe lava, 7

Pakistan, Cachemira earthquake, 77, 91
Paleozoic Era, 10
Pangea, 14
peak, highest volcanic, 46
Pelean eruption, 31
Peléé, Mount (volcano), 31, 47, 57
Pinatubo volcano, 46
plate, tectonic: *See tectonic plate*
Plinian eruption: *See Vesuvian eruption*
pluton, 12
Pompeii, 52–53

- House of the Faun, 54
- Mount Vesuvius volcano eruption of AD 79, 52–53
- reconstruction, 55

Portugal, earthquake of 1755, 77, 91
primary wave (P wave), 62–63
Proterozoic Eon, 11
pyroclastic flow, 37, 51
pyroclasts, 30, 35, 52, 53

R

Rayleigh wave, 63
Richter, Charles, 66
Richter scale, 66
rift zone, 43
Ring of Fire, 28, 46
rocks

- cycle, 9
- distribution on the Earth’s crust, 12
- igneous, 9
- magnetism, 17
- metamorphic, 9
- sedimentary, 9

Rodinia, 10

S

safety measures

- earthquakes, 83, 84–85
- volcanoes, 50–51

St. Helens, Mount, 32–33, 46, 57
San Francisco earthquake of 1906, 23, 91

- clean up, 88
- cost, 87
- damage, 86–87, 88–89
- fire, 87, 89
- reconstruction, 87
- sequence, 86–87

Scotia plate, 77
secondary wave (S wave)

- speed in different materials, 63
- trajectory, 63

seismic area, 76
seismic wave, 61, 62–63
seismograph, 49

- See also seismometer*

seismology, 78, 79, 80–81
seismometer, 78–79, 80
silicates, 8
solfatara, 39
Somalia, 72
South America, 15

- earthquakes, 77, 91
- volcanoes, 36, 47

South America plate, 77
Sri Lanka, 72
stratosphere (layer of the atmosphere), 13
Strombolian eruption, 31
subduction, 46, 76, zone, 14, 16
Sumatra, 73
surface waves, 63
Surtsey Island, formation, 42–43

T

Tambora volcano, 46, 56
Tanzania, 72

tectonic plate, 14–15

- African plate, 77
- Antarctic plate, 76, 77
- Arabian plate, 77
- Australian plate, 76
- Caribbean plate, 76, 77
- Cocos plate, 76, 77
- continental drift, 14
- convection currents, 14
- convergent limit, 14
- divergent boundary, 15
- earthquakes, 18, 76–77
- Eurasian plate, 77
- Fiji plate, 76
- India plate, 77
- Indo-Australian plate, 76
- marine trough, 76
- mountains, 18
- Nazca plate, 77
- North American plate, 77
- ocean ridge, 77
- outward movement, 14
- Pacific plate, 76
- Scotia plate, 77
- South America plate, 77
- streambeds, 23
- subduction, 14, 16, 46, 76
- transforming plate, 76
- tsunami, 68
- volcanoes, 26
- widening, 15

Thailand, 70–71, 73
thermopolium, 55
thermosphere (layer of the atmosphere), 13
tiltrometer, 48
Tropic of Cancer, 41
Tropic of Capricorn, 41
troposphere (layer of the atmosphere), 13
tsunami, 68–69

- coastal damage, 70–71
- detection, 73
- direction, 68
- duration, 72
- earthquakes, 68–69, 85, 91
- Indian Ocean, 72–73

Krakatoa, 34

- origin of the word, 68
- speed, 72
- tectonic plates, 68
- Thailand, 70–71
- volcanoes, 34, 36
- wave height, 69, 72
- wave length, 69
- wave movement, 73

U

United States

- Alaska, earthquake of 1964, 76
- Hawaiian Archipelago, 6–7, 29–30, 31, 36, 41, 44–46, 45, 56
- Loma Prieta earthquake of 1989, 59, 64
- Novarupta volcano, 46
- St. Helens, Mount, 32–33, 46, 57
- San Andreas fault, 23
- San Francisco earthquake of 1906, 23, 86–89, 91
- Yellowstone National Park, 38–39

V

Vanuatu, East Epi volcano, 46
Vesuvian eruption, 31, 32
Vesuvius, Mount (volcano), 47, 52–53, 56, 57
volcanic eruption, 26–27, 30–31

- aftereffects, 35, 36–37
- annual rate, 47
- ash, 30, 51
- dangers, 50
- effusive, 31
- energy released, 35
- explosive, 31
- home safety, 51
- lahars, 51
- Pliny eruption, 52–53
- pyroclastic flows, 51

- rhyolitic, 37
- safety, 50–51
- through time, 56–57
- volcanic island**
 - atolls, 16, 41
 - formation, 41
- volcano**, 24–43
 - basic types, 28–29
 - caldera, 29, 36
 - cinder cone, 28, 36
 - climate change, 56
 - conduit, 30
 - crater, 30
 - critical distance, 51
 - earthquakes, 32, 37
 - eruption: See **volcanic eruption**
 - extinct, 26, 29
 - fissure, 29
 - formation, 26
 - geysers, 38–39
 - Iceland, 42–43
 - igneous intrusions, 29
 - lahars, 36
 - magma chamber, 29, 30
 - monitoring, 48–49
 - parasitic, 29
 - postvolcanic activities, 38–39
 - pyroclastic flow, 37
 - pyroclasts, 30, 35, 52, 53
 - rings of coral, 40–41
 - shield, 28
 - specific volcanoes
 - Avachinsky, 46
 - Caldera Blanca, 29
 - East Epi, 46
 - El Chichón, 57
 - Eldfell, 47, 57
 - Etna, 31, 47
 - Fuji, 28, 46
 - Ilamatepec, 28
 - Incahuasi, 46
 - Kilauea, 28, 31, 44, 46, 56
 - Krafla, 43
 - Krakatoa, 34–35, 46, 57
 - Laki, 56
 - Llullaillaco, 46
 - Maka-O-Puhl, 31
 - Mauna Loa, 31, 46
 - Mauna Ulu, 29
 - Nevado del Ruiz, 36
 - Novarupta, 46
 - Ojos del Salado, 47
 - Peléé, 31, 47, 57
 - Pinatubo, 46
 - St. Helens, 32–33, 46, 57
 - Sajama, 46
 - Tambora, 46, 56
 - Tipas, 46
 - Vesuvius, 47, 52–53, 56, 57
 - stratovolcano, 28
 - structure, 26–27
 - tallest, 46
 - tectonic plate, 26
 - tsunamis, 34, 36
 - volcanic activity, 46–47
 - volcanic islands: See **volcanic island**
 - volcanic plug, 29
 - warning signs, 32–33, 34–35
- volcanology**, 48–49
- Vulcanian eruption**, 31

W

- Waimangu geyser, 38
- Wegener, Alfred, 14

Y

- Yellowstone National Park, 38–39



VOLCANOES AND EARTHQUAKES

*Britannica Illustrated
Science Library*

